

**FORM
5**Rev
02/08**State of Colorado****Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400313037

Date Received:

08/06/2012

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 66571

4. Contact Name: Joan Proulx

2. Name of Operator: OXY USA WTP LP

Phone: (970) 263-3641

3. Address: P O BOX 27757

Fax: (970) 263-3694

City: HOUSTON State: TX Zip: 77227

5. API Number 05-045-20722-00

6. County: GARFIELD

7. Well Name: Cascade Creek

Well Number: 697-04-65A

8. Location: QtrQtr: NWSW Section: 4 Township: 6S Range: 97W Meridian: 6

Footage at surface: Distance: 1498 feet Direction: FSL Distance: 1122 feet Direction: FWL

As Drilled Latitude: 39.548810 As Drilled Longitude: -108.230180

GPS Data:

Data of Measurement: 11/17/2011 PDOP Reading: 1.1 GPS Instrument Operator's Name: S Bonner

** If directional footage at Top of Prod. Zone Dist.: 1734 feet. Direction: FSL Dist.: 551 feet. Direction: FWL

Sec: 4 Twp: 6S Rng: 97W

** If directional footage at Bottom Hole Dist.: 1726 feet. Direction: FSL Dist.: 460 feet. Direction: FWL

Sec: 4 Twp: 6S Rng: 97W

9. Field Name: GRAND VALLEY

10. Field Number: 31290

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 03/02/2012 13. Date TD: 03/18/2012 14. Date Casing Set or D&A: 03/19/2012

15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 9297 TVD** 9233 17 Plug Back Total Depth MD 9241 TVD** 9177

18. Elevations GR 8631 KB 8663

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

CBL/CBL-VDL/GR-CCL
RST/Inelastic Capture Mode/GR-CCL
RST/Sigma Mode/GR-CCL

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	20+0/0	16+0/0	65	0	75	4	0	75	CALC
SURF	14+3/4	9+5/8	36	0	2,745	1,250	0	2,745	CALC
1ST	8+3/4	4+1/2	11.6	0	9,267	1,757	2,170	9,267	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: 03/04/2012

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom
	SURF		86	0	2,745
	SURF		150	0	2,745
	SURF		128	0	2,745
	SURF		80	0	2,745

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
FORT UNION	4,890	6,284	<input type="checkbox"/>	<input type="checkbox"/>	
MESAVERDE	6,284	6,459	<input type="checkbox"/>	<input type="checkbox"/>	
WILLIAMS FORK	6,459	8,675	<input type="checkbox"/>	<input type="checkbox"/>	
CAMEO	8,675	9,084	<input type="checkbox"/>	<input type="checkbox"/>	
ROLLINS	9,084		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

Subsequent Form 5.

As-built data obtained at the conductor.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Joan Proulx

Title: Regulatory Analyst

Date: 8/6/2012

Email: joan_proulx@oxy.com

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
	CMT Summary *	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Directional Survey **	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400313037	FORM 5 SUBMITTED	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	off hold; oper. submits dir. template with prelim form 5	8/23/2012 3:11:25 PM
Permit	on hold; need dir. template	8/10/2012 11:12:51 AM

Total: 2 comment(s)