



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336226 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

198983

Date 02/19/2011	Well Owner KERR MCGEE	Well No. 27-34	Lease PIERSON
County WELD	State COLORADO	Field	
Order to KERR MCGEE OIL & GAS ONSHORE, LP			Charge Code
Address 1999 BROADWAY, SUITE 3200 (XTREME*14)			For Office Use Only
City, State DENVER COLORADO 80202			
Pump Truck No. 1201	Code	Ball Truck No. 1214/1217	Code
Type of Job	Depth	Fr. 561	To
Surface 8 5/8" - C 50 34	Bottom of Surface	Fr. 551	To
Flag	Flag Number 507	Time On 0145	
Production	Pipe Landed 551	Time Off PLUG DOWN 0430	

Reference No.	Description	Qty.	Unit	Unit Price	Amount
	Pump Truck Charge				
	Cement Type TYPE III 100% CYCESS	350	SKS		
	For Mix				
	Calcium Chloride	25%			
	Gel 9 Fl-Coke Water Sack				2044/120.00
	Heating Charge				80012090
	Heating Charge				
	Additional Cement	90	SKS	14.60	
	MIXING RATE 4 BPM		PRE-FLUSH	0404-0406	
	DISP RATE 5 BPM		MIX	0406-0421	
	SLURRY VOL 1.32 CUFT/SK		CHANGE VALVES	0421-0424	
	SLURRY WT 14.8-15.0 PPG		DISPLACE	0424-0430	
	WATER/CEMENT 4.25 GAL/SK		FINAL LTR @	350 PSI	
	TOTAL SLURRY VOL 94 BBLs CEMENT				
	PLUG LANDED @ 1000 PSI				
	WATER TEMP 58°F				

PRE-FLUSH 1.1/10 BBLs H ₂ O	Tax Reference Code	Sub Total				
DISPLACE 1.1/32 BBLs H ₂ O	State 00.29 %	Tax				
CIRCULATE 6 BBLs CEMENT	Disc.	Total				
Track No.	Code	State Mfrg	Nebraska	Colorado	Wyoming	Other
1201		Pump Truck		30		
1217/1214		Ball Truck		30/30		

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By **JIM/OSCAR/STEVE/ADAM**

Received By

Cody Sanders
Customer or His Agent