

FORM
5

Rev
02/08

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400267091

Date Received:

03/30/2012

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type Final completion Preliminary completion

1. OGCC Operator Number: 100185
2. Name of Operator: ENCANA OIL & GAS (USA) INC
3. Address: 370 17TH ST STE 1700
City: DENVER State: CO Zip: 80202-
4. Contact Name: Sheilla Reed-High
Phone: (720) 876-3678
Fax: (720) 876-4678

5. API Number 05-123-34693-00
6. County: WELD
7. Well Name: SLATER Well Number: 4-6-28
8. Location: QtrQtr: NWSE Section: 28 Township: 3N Range: 68W Meridian: 6
Footage at surface: Distance: 1376 feet Direction: FSL Distance: 1695 feet Direction: FEL
As Drilled Latitude: 40.193291 As Drilled Longitude: -105.004433

GPS Data:
Date of Measurement: 03/26/2012 PDOP Reading: 2.6 GPS Instrument Operator's Name: PAT LINDERHOLM

** If directional footage at Top of Prod. Zone Dist.: 1392 feet. Direction: FSL Dist.: 2617 feet. Direction: FEL
Sec: 28 Twp: 3N Rng: 68W

** If directional footage at Bottom Hole Dist.: 1392 feet. Direction: FSL Dist.: 2617 feet. Direction: FEL
Sec: 28 Twp: 3N Rng: 68W

9. Field Name: WATTENBERG 10. Field Number: 90750
11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 01/14/2012 13. Date TD: 01/17/2012 14. Date Casing Set or D&A: 01/20/2012

15. Well Classification:
 Dry Oil Gas/Coalbed Disposal Stratigraphic Enhanced Recovery Storage Observation

16. Total Depth MD 7845 TVD** 7802 17 Plug Back Total Depth MD 7416 TVD** 7327

18. Elevations GR 4962 KB 4975
One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:
CBL

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+/25	8.625		0	1,036	400	0	1,036	CALC
1ST	7+/875	4.5		0	7,826	637	2,880	7,826	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES					
FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
SUSSEX	3,937		<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	6,964		<input type="checkbox"/>	<input type="checkbox"/>	
CODELL	7,214		<input type="checkbox"/>	<input type="checkbox"/>	
J SAND	7,658		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Sheilla Reed-High

Title: Drilling and Compl. Tech. Date: 3/30/2012 Email: sheilla.reedhigh@Encana.com

Attachment Check List

Att Doc Num	Document Name	attached ?	
<u>Attachment Checklist</u>			
400267127	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
400267103	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
<u>Other Attachments</u>			
400267091	FORM 5 SUBMITTED	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400267108	LAS-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400267111	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400267113	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

General Comments

User Group	Comment	Comment Date
Permit	Off hold. Per operator input as built information, CBL received, and BHL due to irregular section.	8/23/2012 12:59:42 PM
Permit	On hold. Requested as built information, Paper CBL, clarification of BHL.	7/19/2012 7:39:36 AM

Total: 2 comment(s)