



WELL NAME: Indian Mesa 32-7-11 #1				FIELD: Ignacio Blanco				LSE#: 045836				
STATE: Colorado				COUNTY: La Plata				FORMATION: Fruitland Coal				
API NO: 05-067-09856				SRF LOC: SWSE 11 32N 7W				SPUD DATE: 09/15/07				
BLM LEASE #:				BHL (Pilot):				TD DATE: 09/19/07				
TD (Pilot): 3615'		TVD (Pilot): 3227'		BHL (Lat 1):		TVD (Lat 1):		CMPL DATE:				
PBTD (Pilot): 3556'		TVD (Lat 2):		BHL (Lat 2):		TVD (Lat 2):		ELEVATION: 6306.4' GL /				
PIPE RECORD								CEMENT & HOLE DATA				
	OD	GRADE	THD	WT/FT	TOP	BTM	# JTS	HOLE SIZE	DEPTH	SX	YIELD (ft3/sk)	TOC
Srf Csg	8 5/8"		STC	24.00#	0'	355'	8	12 1/4"	365'	265	1.17	0'
Prod Csg	5 1/2"	P-110	BTC	17.00#	0'	3608'	79	7 7/8"	3615'	255	2.25	0'
										270	1.82	
Lat # 1 Liner	2 7/8"	J-55		6.5#	3015'	7001'	124	4 3/4"	7001'			
Lat #2 Liner	2 7/8"	J-55		6.5#	3151'	4765'	50	4 3/4"	5527'			
Lat # 3 Liner	2 7/8"	J-55		6.5#	2969'	6477'	118	4 3/4"	6780'			

Created: S. Deater 09-20-2011  
Modified: Dan Graeve 02/20/2012  
Heidi Lehr 05/09/12

<b>PERFORATION RECORD</b>				
DATE	PERFS	ZONE	STATUS	SPF
10/13/2011	3375-3388 3233-3237			
10/13/2011	3164-3168 3136-3153 3123-3134 3115-3120 3107-3111			
10/13/2011	3075-3088 3020-3023			
Tbg Detail as of		Jts	Length	Depth
KB				12.00
2 7/8" 6.5# J-55 EUE 8rd tbg. (new)		89	2895.97	2907.97
Expendable check/ SN			1.10	2909.07
2 7/8" 6.5# J-55 EUE 8rd tbg. (new)		1	32.52	2941.59
Notched collar			0.55	2942.14

