

FORM  
2

Rev  
12/05

# State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400314639

Date Received:

08/10/2012

## APPLICATION FOR PERMIT TO:

1.  Drill,  Deepen,  Re-enter,  Recomplete and Operate

### 2. TYPE OF WELL

OIL  GAS  COALBED  OTHER \_\_\_\_\_  
SINGLE ZONE  MULTIPLE  COMMINGLE

Refiling

Sidetrack

PluggingBond SuretyID

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: Bonnie Lamond Phone: (720)876-5156 Fax: (720)876-6177

Email: bonnie.lamond@encana.com

7. Well Name: Benjamin Federal Well Number: 28-12C1 (K28NW)

8. Unit Name (if appl): Grass Mesa Unit Number: COC056608  
A

9. Proposed Total Measured Depth: 9355

## WELL LOCATION INFORMATION

10. QtrQtr: NESW Sec: 28 Twp: 6S Rng: 93W Meridian: 6

Latitude: 39.494278 Longitude: -107.780438

Footage at Surface: 1584 feet FNL/FSL FSL 2532 feet FEL/FWL FWL

11. Field Name: Mamm Creek Field Number: 52500

12. Ground Elevation: 5954 13. County: GARFIELD

### 14. GPS Data:

Date of Measurement: 06/11/2010 PDOP Reading: 2.8 Instrument Operator's Name: C.D. Slaugh

15. If well is  Directional  Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1670 FSL 240 FWL FWL Bottom Hole: FNL/FSL 1670 FSL 240 FWL FWL  
Sec: 28 Twp: 6S Rng: 93W Sec: 28 Twp: 6S Rng: 93W

16. Is location in a high density area? (Rule 603b)?  Yes  No

17. Distance to the nearest building, public road, above ground utility or railroad: 550 ft

18. Distance to nearest property line: 375 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 320 ft

## 20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Iles	ILES			
Williams Fork	WMFK			

21. Mineral Ownership:  Fee  State  Federal  Indian Lease #: COC054737

22. Surface Ownership:  Fee  State  Federal  Indian

23. Is the Surface Owner also the Mineral Owner?  Yes  No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease?  Yes  No

23b. If 23 is No:  Surface Owners Agreement Attached or  \$25,000 Blanket Surface Bond  \$2,000 Surface Bond  \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T6S-R93W: Sec. 28: W2W2

25. Distance to Nearest Mineral Lease Line: 240 ft 26. Total Acres in Lease: 160

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated?  Yes  No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling?  Yes  No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling?  Yes  No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)?  Yes  No

31. Mud disposal:  Offsite  Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method:  Land Farming  Land Spreading  Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	16	Linepipe	0	40	100	40	0
SURF	12+1/4	9+5/8	36	0	1,403	435	1,403	0
1ST	7+7/8	4+1/2	11.6	0	9,355	820	9,355	0

32. BOP Equipment Type:  Annular Preventer  Double Ram  Rotating Head  None

33. Comments Distance from well to public road is 550'. Intermediate casing will be 200>MSVD; production TOC will be 500' inside intermediate casing.

34. Location ID: 335428

35. Is this application in a Comprehensive Drilling Plan?  Yes  No

36. Is this application part of submitted Oil and Gas Location Assessment?  Yes  No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Bonnie Lamond

Title: Permitting Technician Date: 8/10/2012 Email: bonnie.lamond@encana.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: Matthew Lee Director of COGCC Date: 9/7/2012

#### API NUMBER

05 045 20170 00

Permit Number: \_\_\_\_\_ Expiration Date: 9/6/2014

#### CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- (1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.
- (2) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE GARFIELD COUNTY RULISON-FIELD NOTICE TO OPERATORS IS REQUIRED.
- (3) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE MAMM CREEK FIELD NOTICE TO OPERATORS IS REQUIRED.
- (4) COMPLIANCE WITH THE NOTICE TO OPERATORS DRILLING WELLS IN THE BUZZARD, MAMM CREEK, AND RULISON FIELDS, GARFIELD COUNTY AND MESA COUNTY IS REQUIRED. (PROCEDURES AND SUBMITTAL REQUIREMENTS FOR COMPLIANCE WITH COGCC ORDERS NOS. 1-107, 139-56, 191-22, AND 369-2 (JULY 8, 2010)). SEE ATTACHED NOTICE.
- (5) THE MOISTURE CONTENT OF ANY DRILL CUTTINGS IN A CUTTINGS PIT, TRENCH, OR PILE SHALL BE AS LOW AS PRACTICABLE TO PREVENT ACCUMULATION OF LIQUIDS GREATER THAN DE-MINIMIS AMOUNTS. AT THE TIME OF CLOSURE, THE DRILL CUTTINGS MUST ALSO MEET THE APPLICABLE STANDARDS OF TABLE 910-1.
- (6) NO PORTION OF ANY PIT THAT WILL BE USED TO HOLD LIQUIDS SHALL BE CONSTRUCTED ON FILL MATERIAL, UNLESS THE PIT AND FILL SLOPE ARE DESIGNED AND CERTIFIED BY A PROFESSIONAL ENGINEER, SUBJECT TO REVIEW AND APPROVAL BY THE DIRECTOR PRIOR TO CONSTRUCTION OF THE PIT. THE CONSTRUCTION AND LINING OF THE PIT SHALL BE SUPERVISED BY A PROFESSIONAL ENGINEER OR THEIR AGENT. THE ENTIRE BASE OF THE PIT MUST BE IN CUT.
- (7) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 360 FEET DEEP.

**Attachment Check List**

Att Doc Num	Name
400314639	FORM 2 SUBMITTED

Total Attach: 1 Files

**General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>
Permit	Per oper. no changes to original APD; no attachments needed. Location built w/ 13 prod. wells. Passed loc. inspection 4/5/12. No LGD or public comments. Final Review--passed.	9/5/2012 8:12:57 AM
LGD	Passed DB	8/27/2012 3:01:37 PM
Permit	Blanket waivers signed by offset mineral owners for BHL <600' from unit boundary in well file.	8/27/2012 1:50:54 PM

Total: 3 comment(s)

**BMP**

<b><u>Type</u></b>	<b><u>Comment</u></b>

Total: 0 comment(s)