



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600374

Date	2-21-12	Well Owner	Kerr McGee	Well No.	21-2	Lease	DARON
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (XTREME-15)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Fl.	946		
Surface	8 5/8" CSG-24H	Bottom of Surface		Fl.	944		
Plug		Plug Landed @	900	Fl.	Time On	11:00	
Production		Pipe Landed @	944	Fl.	Plug Down	19:15	
Description		Qty.	Meas.	Unit Price	Amount		
Set Up Charge		1					
Cement Neat	TYPE III	1000	SKS				
Poz. Mix							
Calcium Chloride		2.5	%				
Gel %	Flo-Cete 1/4 # Per Sack						
Mileage Charge	204 9080	246	Miles				
Fuel Surcharge	80012090	246	MILES				
Additional Cement			SKS				
Mixing Rate	4 BPM	Pre-Flush	1817	-1824			
Disp. Rate	5 BPM	Mixing	1824	-1900			
Slurry Vol.	1.32 Cu.Ft./Sk	Change Valves	1900	-1903			
Slurry Wt.	14.8 - 15.0 PPG	Displacement	1903	-1915			
Water/Cement	6.25 Gal/SK						
Water Temp.	57°						
Total Slurry Vol.	141.0	BBLS Cement					
Landed Plug @	300	PSI/Final Lift @	280	PSI			
Pre-Flush W/	30	BBLS H ₂ O	Tax Reference Code	Sub Total			
Displace W/	57.2	BBLS H ₂ O	State	CO 2.9%	Tax		
Circulate	5	BBLS Cement		Total			
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		82			
1218/1216		Bulk Truck		82/82			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JOE, ERNIE, CHRIS

Received By [Signature]
Customer or His Agent