



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600363

Date <u>2/25/12</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>30-2</u>	Lease <u>DACON</u>
County <u>Weld</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (Xtreme #15)</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	Fl. <u>955</u>	
<u>Surface</u> <u>9 5/8" (154-24")</u>	Bottom of Surface	Fl. <u>945</u>	
Plug	Plug Landed @ <u>901</u>	Fl. Time On <u>1830</u>	
Production	Pipe Landed @ <u>945</u>	Fl. Plug Down <u>2030</u>	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>✓ Type III</u>	590	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cote 1/4 # Per Sack				
Mileage Charge <u>205729</u>	246	Miles		
Fuel Surcharge <u>\$201109</u>	246	Miles		
Additional Cement		SKS		
Mixing Rate 4 BPM	Pre-Flush	1944-	1950	
Disp. Rate 5 BPM	Mixing	1950-	2016	
Slurry Vol. 1.32 ³ Cu.Ft./Sk	Change Valves	2016-	2019	
Slurry Wt. 14.8 - 15.0 PPG	Displacement	2019-	2030	
Water/Cement 6.25 Gal/SK				
Water Temp. <u>103°F</u>				
Total Slurry Vol. <u>130.7</u>	BBLs Cement			
Landed Plug @ <u>450</u>	PSI/Final Lift @	PSI		
Pre-Flush Wt <u>30</u>	BBLs H ₂ O	Tax Reference Code	Sub Total	
Displace Wt <u>57.3</u>	BBLs H ₂ O	State CO 2.9%	Tax	
Circulate <u>3</u>	BBLs Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1208</u>		Pump Truck		<u>82</u>			
<u>1214/1215</u>		Bulk Truck		<u>82/82</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By

Received By

Customer or His Agent