



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

## 600427

Date <u>03-19-12</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>32-2</u>	Lease <u>DACONO</u>
County <u>WELD</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil &amp; Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (XTREME#15)</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	Fl. <u>946</u>	
Surface <u>8 5/8" CSG-24#</u>	Bottom of Surface	Fl. <u>936</u>	
Plug	Plug Landed @ <u>892</u>	Fl. Time On <u>0750</u>	
Production	Pipe Landed @ <u>936</u>	Fl. Plug Down <u>1000</u>	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>TYPE III</u>	<u>590</u>	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cete 1/4 # Per Sack				
Mileage Charge	<u>246</u>	Miles		
Fuel Surcharge	<u>246</u>	MILES		
Additional Cement		SKS		
Mixing Rate 4 BPM	Pre-Flush	<u>0913</u>	<u>0920</u>	
Disp. Rate 5 BPM	Mixing	<u>0920</u>	<u>0946</u>	
Slurry Vol. 1.32 <sup>3</sup> Cu.Ft./Sk	Change Valves	<u>0946</u>	<u>0949</u>	
Slurry Wt. 14.8 - 15.0 PPG	Displacement	<u>0949</u>	<u>1000</u>	
Water/Cement 6.25 Gal/SK				
Water Temp. <u>60°F</u>				
Total Slurry Vol. <u>138.8</u>	BBLS Cement			
Landed Plug @ <u>500</u>	PSI/Final Lift @ <u>250</u>	PSI		
Pre-Flush W/ <u>30</u>	BBLS H <sub>2</sub> O	Tax Reference Code	Sub Total	
Displace W/ <u>56.7</u>	BBLS H <sub>2</sub> O	State <u>CO 2.9%</u>	Tax	
Circulate <u>6</u>	BBLS Cement		Total	

Duaine Bell

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1208</u>		Pump Truck		<u>82</u>			<u>WBS/WO/CC 2051830</u>
<u>1207/1217</u>		Bulk Truck		<u>82/82</u>	G/L Acct		<u>80012096</u>

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JUSTIN, EVAN, STEVE, CHAS

Received By

*[Signature]*  
Customer or His Agent