

FORM
5A

Rev
06/12

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400325621

Date Received:

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 47120
2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP
3. Address: P O BOX 173779
City: DENVER State: CO Zip: 80217-
4. Contact Name: JOEL MALEFYT
Phone: (720) 929-6828
Fax: (720) 929-7828

5. API Number 05-123-33810-00
6. County: WELD
7. Well Name: DACONO
Well Number: 22-2
8. Location: QtrQtr: SENW Section: 2 Township: 1N Range: 68W Meridian: 6
9. Field Name: WATTENBERG Field Code: 90750

Completed Interval

FORMATION: CODELL Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 04/20/2012 End Date: 04/20/2012 Date of First Production this formation: 08/17/2012

Perforations Top: 7856 Bottom: 7872 No. Holes: 64 Hole size: 0.4

Provide a brief summary of the formation treatment: Open Hole: ☐

Frac CODL down 4.5" casing w/ 198,366 gal slickwater w/ 150,160# 40/70, 4,000# 20/40.
Broke @ 3,267 psi @ 3 bpm. ATP=4,251 psi; MTP=4,995 psi; ATR=60.1 bpm; ISDP=2,846 psi

This formation is commingled with another formation: ☐ Yes ☒ No

Total fluid used in treatment (bbl): 3575 Max pressure during treatment (psi): 4995

Total gas used in treatment (mcf): Fluid density at initial fracture (lbs/gal): 8.30

Type of gas used in treatment: Max frac gradient (psi/ft):

Total acid used in treatment (bbl): Number of staged intervals: 1

Recycled water used in treatment (bbl): Flowback volume recovered (bbl):

Fresh water used in treatment (bbl): Disposition method for flowback: DISPOSAL

Total proppant used (lbs): 154160 Rule 805 green completion techniques were utilized: ☒

Reason why green completion not utilized:

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 08/22/2012 Hours: 24 Bbl oil: 50 Mcf Gas: 100 Bbl H2O: 0

Calculated 24 hour rate: Bbl oil: 50 Mcf Gas: 100 Bbl H2O: 0 GOR: 2000

Test Method: FLOWING Casing PSI: 1650 Tubing PSI: Choke Size: 12/64

Gas Disposition: SOLD Gas Type: WET Btu Gas: 1315 API Gravity Oil: 49

Tubing Size: Tubing Setting Depth: Tbg setting date: Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

** Bridge Plug Depth: ** Sacks cement on top: ** Wireline and Cement Job Summary must be attached.

Comment:

--

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: JOEL MALEFYT

Title: REGULATORY ANALYST

Date: _____

Email: JOEL.MALEFYT@ANADARKO.COM
:

Attachment Check List

Att Doc Num	Name

Total Attach: 0 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)