

FORM
5Rev
02/08

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400247992

Date Received:

05/17/2012

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 47120

4. Contact Name: JOEL MALEFYT

2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP

Phone: (720) 929-6828

3. Address: P O BOX 173779

Fax: (720) 929-7828

City: DENVER State: CO Zip: 80217-

5. API Number 05-123-34484-00

6. County: WELD

7. Well Name: CAMP

Well Number: 2C-25HZ

8. Location: QtrQtr: SWSE Section: 25 Township: 3N Range: 66W Meridian: 6

Footage at surface: Distance: 725 feet Direction: FSL Distance: 1981 feet Direction: FEL

As Drilled Latitude: 40.191206 As Drilled Longitude: -104.722902

GPS Data:

Data of Measurement: 02/28/2012 PDOP Reading: 1.3 GPS Instrument Operator's Name: RENEE DOIRON

** If directional footage at Top of Prod. Zone Dist.: 522 feet. Direction: FSL Dist.: 1812 feet. Direction: FEL

Sec: 25 Twp: 3N Rng: 66W

** If directional footage at Bottom Hole Dist.: 474 feet. Direction: FNL Dist.: 1788 feet. Direction: FEL

Sec: 25 Twp: 3N Rng: 66W

9. Field Name: WATTENBERG

10. Field Number: 90750

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 11/18/2011 13. Date TD: 01/28/2012 14. Date Casing Set or D&A: 01/30/2012

15. Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 11925 TVD** 7417 17 Plug Back Total Depth MD 11910 TVD** 7417

18. Elevations GR 5077 KB 5094

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

LWD, CBL, MUD LOG

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	9+5/8	36	0	885	420	0	885	VISU
1ST	8+3/4	7+0/0	26	0	7,646	735	200	7,646	CBL
1ST LINER	6+1/8	4+1/2	11.6	6753	11,910				CALC

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
SHANNON	4,970		<input type="checkbox"/>	<input type="checkbox"/>	
SHARON SPRINGS	7,151		<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	7,232		<input type="checkbox"/>	<input type="checkbox"/>	
CODELL	7,721		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: JOEL MALEFYTTitle: REGULATORY ANALYST Date: 5/17/2012 Email: JOEL.MALEFYT@ANADARKO.COM**Attachment Check List**

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400253000	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400263470	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400247992	FORM 5 SUBMITTED	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400263471	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

User Group	Comment	Comment Date
Permit	top of Codell 7721' per operator.	9/5/2012 10:42:22 AM
Permit	ON HOLD: requesting formation top for CODL.	8/14/2012 2:35:48 PM

Total: 2 comment(s)