



CEMENTER'S WELL SERVICE, INC.
P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600470

Date <u>4-1-12</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>11-36</u>	Lease <u>NORTHGLENN STATE</u>
County <u>WELD</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (XTREME-11)</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	Fl.	
(Surface) <u>8 5/8" CSG-747</u>	Bottom of Surface	Fl. <u>1040</u>	
Plug	Plug Landed @ <u>996</u>	Fl. Time On <u>0515</u>	
Production	Pipe Landed @ <u>1040</u>	Fl. Plug Down <u>0745</u>	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>TYPE III 100% EXCESS</u>	<u>660</u>	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Crete 1/4 # Per Sack				
Mileage Charge <u>2051107</u>	<u>240</u>	Miles		
Fuel Surcharge	<u>240</u>	MILES		
Additional Cement <u>80012090</u>	<u>40</u>	SKS		
Mixing Rate <u>4 BPM</u>	Pre-Flush	<u>0640</u>	<u>0648</u>	
Disp. Rate <u>5 BPM</u>	Mixing	<u>0648</u>	<u>0729</u>	
Slurry Vol. <u>1.32 Cu.FL/Sk</u>	Change Valves	<u>0729</u>	<u>0732</u>	
Slurry Wt. <u>14.8 - 15.0 PPG</u>	Displacement	<u>0732</u>	<u>0745</u>	
Water/Cement <u>6.25 Gal/SK</u>				
Water Temp. <u>58°F</u>				
Total Slurry Vol. <u>164.5</u>	BBLs Cement			
Landed Plug @ <u>900</u>	PSI/Final Lift @ <u>400</u>	PSI		
Pre-Flush W/ <u>30</u>	BBLs H ₂ O	Tax Reference Code	Sub Total	
Displace W/ <u>63.3</u>	BBLs H ₂ O	State <u>CO 2.9%</u>	Tax	
Circulate <u>5</u>	BBLs Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
-----------	------	---------------	----------	----------	---------	-------	---------------