



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600352

Date <u>2/13/2012</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>2C-33HZ</u>	Lease <u>RICE</u>
County <u>WELD</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (major #44)</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	Fl. <u>724</u>	
Surface <u>9 5/8" CSG 3L# 13 1/2" HD</u>	Bottom of Surface	Fl. <u>712</u>	
Plug	Plug Landed @ <u>670</u>	Fl. Time On <u>0340</u>	
Production	Pipe Landed @ <u>712</u>	Fl. Plug-Down <u>0630</u>	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>TYPE III</u>	<u>530</u>	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Crete 1/4 # Per Sack				
Mileage Charge <u>2059185</u>	<u>11.2</u>	Miles		
Fuel Surcharge <u>80012090</u>	<u>11.2</u>	MILES		
Additional Cement	<u>60</u>	SKS		
Mixing Rate <u>4 BPM</u>	Pre-Flush	<u>0540</u>	<u>0546</u>	
Disp. Rate <u>5 BPM</u>	Mixing	<u>0546</u>	<u>0617</u>	
Slurry Vol. <u>1.32³ Cu.Ft./Sk</u>	Change Valves	<u>0617</u>	<u>0620</u>	
Slurry Wt. <u>14.8 - 15.0 PPG</u>	Displacement	<u>0620</u>	<u>0630</u>	
Water/Cement <u>6.25 Gal/SK</u>				
Water Temp. <u>40</u>				
Total Slurry Vol. <u>139.7</u>	BBLS Cement			
Landed Plug @ <u>1030</u>	PSI/Final Lift @ <u>240</u>	PSI		
Pre-Flush W/ <u>30</u>	BBLS H ₂ O	Tax Reference Code	Sub Total	
Displace W/ <u>9.7</u>	BBLS H ₂ O	State <u>CO 2.9%</u>	Tax	
Circulate <u>7</u>	BBLS Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1201</u>		Pump Truck		<u>54</u>			
<u>1216/1214</u>		Bulk Truck		<u>54/54</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Jim / Adam / Jason

Received By Randy Cull
Customer or His Agent