



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 236220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600544

Date	7-9-12	Well Owner	Kerr McGee	Well No.	24-2	Lease	LAMBRECHT
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (XTREME #11)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth	Fl. 958				
Surface	8 5/8" CSG-24#	Bottoms of Surface	Fl. 948				
Plug		Plug Landed @	903	Fl.	Time On	2030	
Production		Pipe Landed @	948	Fl.	Plug Down	2230	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	600	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Crete 1/4 # Per Sack				
Mileage Charge	180	Miles		
Fuel Surcharge	180	MILES		
Additional Cement		SKS		
Mixing Rate	4 BPM	Pre-Flush	2132	2140
Disp. Rate	5 BPM	Mixing	2140	2215
Slurry Vol.	1.32 Cu.FL/Sk	Change Valves	2215	2218
Slurry Wt.	14.8 - 15.0 PPG	Displacement	2218	2230
Water/Cement	6.25 Gal/SK			
Water Temp.	70°F			
Total Slurry Vol.	141.0	BBLs Cement		
Landed Plug @	300	PSI/Final Lift @ 280	PSI	
Pre-Flush W/	30	BBLs H ₂ O	Tax Reference Code	Sub Total
Displace W/	57.4	BBLs H ₂ O	State CO 2.9%	Tax
Circulate	5	BBLs Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Duaine Bell	Other	Total Mileage
1202		Pump Truck		60	User ID ZDSB4		
1214/1218		Bulk Truck		60/60	WBS/WO/CC 2046008		

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to change without notice.

Delivered By JOE, JOSH C., JOSH A., ERNIE

Received By [Signature]
Customer or His Agent