

FORM
5

Rev
02/08

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400309347

Date Received:

07/25/2012

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type Final completion Preliminary completion

1. OGCC Operator Number: 100322 4. Contact Name: EILEEN ROBERTS
2. Name of Operator: NOBLE ENERGY INC Phone: (303) 2284330
3. Address: 1625 BROADWAY STE 2200 Fax: (303) 2284286
City: DENVER State: CO Zip: 80202

5. API Number 05-123-34421-00 6. County: WELD
7. Well Name: Wells Ranch USX Well Number: AA25-67-1HN
8. Location: QtrQtr: NWNW Section: 25 Township: 6N Range: 63W Meridian: 6
Footage at surface: Distance: 1114 feet Direction: FNL Distance: 302 feet Direction: FWL
As Drilled Latitude: 40.461690 As Drilled Longitude: -104.393540

GPS Data:

Data of Measurement: 05/10/2012 PDOP Reading: 2.3 GPS Instrument Operator's Name: Paul Tappy

** If directional footage at Top of Prod. Zone Dist.: 1591 feet. Direction: FNL Dist.: 711 feet. Direction: FWL
Sec: 25 Twp: 6N Rng: 63W

** If directional footage at Bottom Hole Dist.: 1546 feet. Direction: FNL Dist.: 527 feet. Direction: FEL
Sec: 25 Twp: 6N Rng: 63W

9. Field Name: CROW CREEK 10. Field Number: 13610
11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 11/25/2011 13. Date TD: 12/04/2011 14. Date Casing Set or D&A: 12/12/2011

15. Well Classification:

Dry Oil Gas/Coalbed Disposal Stratigraphic Enhanced Recovery Storage Observation

16. Total Depth MD 11001 TVD** 6568 17 Plug Back Total Depth MD 10985 TVD** 6568

18. Elevations GR 4815 KB 4839

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

CBL/GRL/CCL.

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	18+1/2	16+0/0	84.00	0	124	160	0	124	CALC
SURF	13+3/4	9+5/8	36.00	0	573	319	0	573	VISU
1ST	8+3/4	7+0/0	26.00	0	6,997	575	1,530	6,997	CBL
2ND	6+1/8	4+1/2	11.60	0	10,985				

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
SUSSEX	4,399		<input type="checkbox"/>	<input type="checkbox"/>	
SHANNON	4,949		<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	6,677		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Eileen Roberts

Title: Regulatory Specialist Date: 7/25/2012 Email: eroberts@nobleenergyinc.com

Attachment Check List

Att Doc Num	Document Name	attached ?	
Attachment Checklist			
400309474	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
400309475	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
Other Attachments			
400309347	FORM 5 SUBMITTED	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400309468	LAS-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400309481	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

General Comments

User Group	Comment	Comment Date
Permit	Off Hold. Operator provided corrected production footages.	9/11/2012 3:04:06 PM
Permit	On Hold requested verification of production footages.	9/11/2012 11:50:44 AM

Total: 2 comment(s)