

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

TICKET NUMBER 34445
LOCATION Oakley, KS
FOREMAN Kelly Gabe

FIELD TICKET & TREATMENT REPORT CEMENT

COLO

DATE	CUSTOMER #	WELL NAME & NUMBER		SECTION	TOWNSHIP	RANGE	COUNTY
5-2-12	9160	Mahalo #7		29	10S	55 W	Lincoln
CUSTOMER		Wheipking Fullerton Limon COLO 55 ZINTO					
MAILING ADDRESS				TRUCK #	DRIVER	TRUCK #	DRIVER
				399	Damon M		
CITY		STATE	ZIP CODE	4160	Wes F		

JOB TYPE <u>Surface</u>	HOLE SIZE <u>12 1/4</u>	HOLE DEPTH <u>325</u>	CASING SIZE & WEIGHT <u>8 5/8 24 #</u>
CASING DEPTH <u>298'</u>	DRILL PIPE _____	TUBING _____	OTHER _____
SLURRY WEIGHT <u>148</u>	SLURRY VOL _____	WATER gal/sk _____	CEMENT LEFT in CASING <u>20'</u>
DISPLACEMENT <u>17 1/2</u>	DISPLACEMENT PSI _____	MIX PSI _____	RATE _____

REMARKS: safety Meeting, rigged up on well, hooked up to circulate mixed 155 SKS Com 3% CC 2% gel, released plug, displaced with 17 1/2 bbl water.

Cement & Circle

approx. 7 bbl top it

Thank You
Kelly & crew

[illegible]

Ravin 3737

5:00 P.M.
AUTHORIZATION

Ralph Stensly

249523

TITLE DRUG SUPPLY

DATE 5-2-12

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.



CONSOLIDATED
Oil Well Services, LLC

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

TICKET NUMBER 36969

LOCATION Oakley, KS

FOREMAN Kelly Gabe

FIELD TICKET & TREATMENT REPORT
CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER		SECTION	TOWNSHIP	RANGE	COUNTY
6-30-72	9160	Mahalo #7		29	103	55 ^W	Colo Lincoln
CUSTOMER		Mailing Address					
		Whelpking Fullerton					
CITY		STATE	ZIP CODE				
JOB TYPE		HOLE SIZE					
Prod		7 1/2"					

JOB TYPE <u>Prod</u>	HOLE SIZE <u>7 7/8</u>	HOLE DEPTH <u>7890</u>	CASING SIZE & WEIGHT <u>5 1/2 17 lb</u>
CASING DEPTH <u>9884</u>	DRILL PIPE _____	TUBING <u>3 in 38.68'</u>	OTHER <u>28' @ 4659'</u>
SLURRY WEIGHT <u>14 #</u>	SLURRY VOL _____	WATER gal/sk _____	CEMENT LEFT in CASING <u>38.68'</u>
DISPLACEMENT <u>182 bbl</u>	DISPLACEMENT PSI _____	MIX PSI _____	RATE <u>6 1/2 bbl/min</u>
REMARKS: <u>Safety meeting, Ran float equip. turbos on Jt # 2, 3, 4, 13, 15</u> <u>16, 17, 18, 19, 20, 22, 24 reg. cent # 22, 29 Baskets # 2, 77, Pctop # 28</u> <u>Ran logs & circulated for 1 1/2 hrs. ran pipe to bottom circulated 1 1/2 hr.</u> <u>pumped 5 bbl water, mud flush, 5 bbl water, mixed 10 SKS RH 10 SK MH</u> <u>mixed 265 SKS class H 10% gel + 5 # Kalsec 120 gel, cleaned Plumps & line</u> <u>released Plug, displaced with 182 bbl water, released pressure & floathole</u> <u>left 900# Plug landed @ 1500 #</u>			

Thank You
Walter Lake

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401P	1	PUMP CHARGE		
5406	100	MILEAGE	4.05	405.00
1115A	285 SKS	Class Hcement	5.00	500.00
1111	1360#	Salt	19.30	5500.50
1110A	1425#	Kol-seal	.45	612.00
1118B	536#	Bentonite	.56	298.00
1107	71#	Flo-seal	.25	134.00
1107A	13.4	ton Mileage delivery	2.82	200.22
1144G	500 gal	mud flush	1.67	2237.80
4159	1	5 1/2 AFu float shoe (I)	1.00	500.00
4454	1	5 1/2 latchdown Assm. (r)	413.00	413.00
4136	12	5 1/2 Turbo centralizers (r)	303.00	303.00
4130	2	5 1/2 centralizer (r)	72.00	864.00
4104	2	5 1/2 basket (I)	58.00	116.00
4285	1	5 1/2 Port collar	276.00	552.00
			2075.00	2075.00
				18,865.53
				1885.55
				16969.97
				847.15
				17817.12

n 3737

3:00 AM

AUTHORIZATION

TITLE CC - Martin

DATE 6-30-72

DATE 6-30-12
:knowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's
count records, at our office, and conditions of service on the back of this form are in effect for services identified on this form:



**FIELD TICKET & TREATMENT REPORT
CEMENT**

TICKET NUMBER 36976
LOCATION Oakley, KS
FOREMAN Kelly Gabel
ORT Wait Dinkel

DATE	CUSTOMER #	WELL NAME & NUMBER		SECTION	TOWNSHIP	RANGE	COUNTY
7-9-12	9160	Mahalo #7		39	105	55W	Lincoln
CUSTOMER Wheipking Fullerton				Limon COLO 65 E, S, E into			
MAILING ADDRESS				TRUCK #	DRIVER	TRUCK #	DRIVER
CITY				STATE	ZIP CODE		
JOB TYPE Post collar				HOLE SIZE	HOLE DEPTH		

JOB TYPE <u>Post collar</u>	HOLE SIZE _____	HOLE DEPTH _____	CASING SIZE & WEIGHT <u>5 1/2</u>
CASING DEPTH _____	DRILL PIPE _____	TUBING <u>2 7/8</u>	OTHER <u>DCO 4665</u>
SLURRY WEIGHT <u>135</u>	SLURRY VOL _____	WATER gal/sk _____	CEMENT LEFT in CASING _____
DISPLACEMENT <u>26</u>	DISPLACEMENT PSI _____	MIX PSI _____	RATE _____
REMARKS: <u>10 ft</u>			

REMARKS: safety meeting, rigged up on well, pressured tool to 1500#, opened tool, mixed 250 lbs 60/40 Poz 670 gel 2% CC 1/4" Flo-seal, displaced with 26 bbl water, closed tool, pressured to 1500# to make sure tool was closed, ran bats tubing, reversed out, washed out pump & lines

[illegible]

Ravin 3737

5:00 PM

AUTHORIZATION Woods Galt

TITLE

DATE 7-9-12

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.

251074



PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT
CEMENT

TICKET NUMBER 37018
LOCATION Oakley, KS
FOREMAN Kelly Gabe

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
8-12	9160	Mahallo #7	29	10 ^S	55 ^W	Colo Lincoln
CUSTOMER Wheip King Fullerton						
MAILING ADDRESS			TRUCK #	DRIVER	TRUCK #	DRIVER
			309	Jerry Y		
			456	Thomas B		
				Joe B		
CITY			STATE			
			ZIP CODE			
JOB TYPE			HOLE SIZE			

JOB TYPE <u>SPUR</u>	HOLE SIZE _____	HOLE DEPTH _____	CASING SIZE & WEIGHT <u>5 1/2 17#</u>
CASING DEPTH _____	DRILL PIPE _____	TUBING <u>2 3/8</u>	OTHER <u>7 1/8 @ 4623</u>
SLURRY WEIGHT <u>152</u>	SLURRY VOL. _____	WATER gal/sk _____	CEMENT LEFT in CASING _____
DISPLACEMENT <u>22 3/4</u>	DISPLACEMENT PSI _____	MIX PSI _____	RATE _____

REMARKS: safety meeting, rigged up on well, loaded backside & pressured to 500#, loaded tubing & took injection rate of $2\frac{1}{2}$ bbl @ 600#. mixed 200 sks com, displaced down past packer, staged on cement, spotted sand on plug pressured to 2000#, released pressure, squeeze held. released packer, reversed out, pulled 3 stands pressured to 500# shut in. washed pumps & lines, rigged down

Thank You
Kelly & crew

[illegible]

Ravin 3737

6:25 PM

AUTHORIZTION

TITLE

SALES TAX	247.81
ESTIMATED TOTAL	16406.51
DATE	9-17-13

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.

251378