



CEMENTER'S WELL SERVICE, INC.
P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

200519

Date <u>5/20/2012</u>	Well Owner <u>P.D.C</u>	Well No. <u>26M-223</u>	Lease <u>CARMICHAEL</u>
County <u>WELD</u>	State <u>COLORADO</u>		Field
Charge to <u>PETROLEUM DEVELOPMENT CORP</u>		ZJBS	Charge Code
Address <u>1775 SHERMAN STREET, STE 3000 (ENSTADT #32)</u>		AFE	For Office Use Only
City, State <u>DENVER COLORADO 80203</u>		Coding	<u>8/00-112</u>
Pump Truck No. <u>1201</u>	Code	Bulk Truck No. <u>1217/1218</u>	Code
Type of Job		Depth	Fl. <u>917</u> By
Surface <u>9 5/8" CSG 36" 13 7/4 HOLE</u>		Bottom of Surface	Fl. <u>910</u> To
Plug		Plug Landed @ <u>866</u>	Fl. Time On <u>1100</u>
Production		Pipe Landed @ <u>910</u>	Fl. Time Off <u>PUG DOWN 1230</u>

Reference No.	Description	Qty.	Meas.		
	Pump Truck Charge				
	Cement Neat ✓	810	SKS		
	Poz. Mix				
	Calcium Chloride	3010			
	Gel % Flo-Cele 1/4 #Per Sack				
	Handling Charge				
	Hauling Charge				
	Additional Cement				
95 1/8"	GUIDE SHOE	1			
"	CEMENT BASKET	1			
"	CENTRALIZERS	8		80	
"	REFL FLOAT INSERT	1			
	BOX THREAD LOCK	1			
MIX RATE 4 BPM		SLURRY VOL 1.19 CU FT 3/SK			
DISP RATE 5 BPM		SLURRY WGT 14.8-15.0 PPG			
PLUG LANDED @ 1050 PSI		TOTAL SLURRY VOL 170.2 BBLs CEMENT			
Remarks: PRE-FLUSH W/ 30 BRLS H ² O		Tax Reference Code		Sub Total	
DISPLACE W/ 16.9 BBLS H ² O		State CO 2.9 %		Tax	
CIRCULATE 1.6 BBLS CEMENT		Disc.		Total	
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming
1201		Pump Truck		44	
1217/1218		Bulk Truck		44/44	

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is so

Delivered By Jim/Tony/WILL/CRES

Received By

Gene Danner
Customer or His Agent