

WPX Energy Rocky Mountain Company, LLC

Jolley KP 11-27

Kokopelli Field

SHL 255' FNL 487' FEL (NE/4 NE/4) BHL 147' FNL 724' FWL (NW/4 NW/4, Sec. 27, T6S, R91W)

Section 28-T6S-R91W 6th PM

Garfield County, Colorado

Formation Tops

(Measured Depths)

Conductor 24" Hole 16" casing/liner 110' w/37 sks cmt

Cmt @ Surface - (Cmt circ to surf during cmt job)

9 5/8" 32.3# ppf Csg. Set @ 1351'

In 12 1/4" Hole W/370 Sks. Cmt

Top Of Cement 4,172' (CBL)

Tubing String: 2-3/8" Set @7404'

6106-6400' Mesaverde

6501-6769' Mesaverde

6817-7063' Mesaverde

7133-7382' Mesaverde

7420-7656' Mesaverde

7699-7846' Mesaverde

7911-8183' Mesaverde/Cameo

8211-8303' Rollins

PBTD @ 8415'

TMD @ 8477'

TVD @ 8317'

4-1/2", 11.6 ppf. Csg. Set @ 8452' W/1585 sks Cmt