

FORM

2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400315238

Date Received:

08/21/2012

PluggingBond SuretyID

20040071

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
 SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☒

Refiling ☒Sidetrack ☐3. Name of Operator: ANTERO RESOURCES PICEANCE CORPORATION4. COGCC Operator Number: 100795. Address: 1625 17TH ST STE 300City: DENVER State: CO Zip: 802026. Contact Name: Shauna Redican Phone: (303)357-6820 Fax: (303)357-7315Email: sredican@anteroresources.com7. Well Name: Valley Farms Well Number: D4

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 8471

WELL LOCATION INFORMATION

10. QtrQtr: NENW Sec: 15 Twp: 6S Rng: 92W Meridian: 6Latitude: 39.531126 Longitude: -107.653189

Footage at Surface: 1095 feet FNL 2637 feet FWL
 FNL/FSL FEL/FWL

11. Field Name: Mamm Creek Field Number: 5250012. Ground Elevation: 5533 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 10/15/2008 PDOP Reading: 1.1 Instrument Operator's Name: Frank W. Harrington15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
677 FNL 2320 FWL 677 FNL 2320 FWL
 Sec: 15 Twp: 6S Rng: 92W Sec: 15 Twp: 6S Rng: 92W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No17. Distance to the nearest building, public road, above ground utility or railroad: 362 ft18. Distance to nearest property line: 100 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 300 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Iles	ILES	191-25	320	N/2
Williams Fork	WMFK	523-2	320	N/2

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

See lease map previously submitted.

25. Distance to Nearest Mineral Lease Line: 664 ft

26. Total Acres in Lease: 2356

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☒ Disposal Facility Other: Onsite if app (See

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	16	55#	0	60	177	60	0
SURF	12+1/4	8+5/8	24/32#	0	1,000	416	1,000	0
1ST	7+7/8	4+1/2	11.6#	0	8,471	763	8,471	

32. BOP Equipment Type: ☐ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments I certify that all conditions in the original permit are the same except the updated casing and cement program. There have been no other changes to land use, well construction or the lease. This Refile Form 2 does not require a Form 2A because the pad has been constructed, a closed loop system is being used so no pits need to be constructed, the refiled well will not require any expansion / additional surface disturbance of the pad. The location is not in a wildlife restricted surface occupancy area (RSO); consultation with CDOW is not required and the location does not require a variance from any of the rules listed in Rule 306.d.(1).(A).(ii).; consultation with CDPHE is not required. Please note this well is an exception location to Rule 603a(2) however we were granted a variance for this pad prior to construction by providing your office with signed property line waivers from both affected surface owners when permits were originally filed for this pad location so we have not attached new waivers. #31 Mud Disposal: Antero will bury onsite if disposal meets Table 910 and if there is a provision in SUA which allows for such operation. TOP OF CEMENT OF 1ST STRING/PRODUCTION CASING WILL BE >500 FEET ABOVE TOP OF GAS.

34. Location ID: 335534

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☒ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Shauna Redican

Title: Permit Representative

Date: 8/21/2012

Email: sredican@anteroresources.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: Matthew Lee Director of COGCC Date: 9/13/2012

API NUMBER

05 045 18338 00

Permit Number: _____ Expiration Date: 9/12/2014

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

(1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

(2) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE GARFIELD COUNTY RULISON-FIELD NOTICE TO OPERATORS IS REQUIRED.

(3) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE MAMM CREEK FIELD NOTICE TO OPERATORS IS REQUIRED.

(4) COMPLIANCE WITH THE NOTICE TO OPERATORS DRILLING WELLS IN THE BUZZARD, MAMM CREEK, AND RULISON FIELDS, GARFIELD COUNTY AND MESA COUNTY IS REQUIRED. (PROCEDURES AND SUBMITTAL REQUIREMENTS FOR COMPLIANCE WITH COGCC ORDERS NOS. 1-107, 139-56, 191-22, AND 369-2 (JULY 8, 2010)). SEE ATTACHED NOTICE.

(5) THE MOISTURE CONTENT OF ANY DRILL CUTTINGS IN A CUTTINGS PIT, TRENCH, OR PILE SHALL BE AS LOW AS PRACTICABLE TO PREVENT ACCUMULATION OF LIQUIDS GREATER THAN DE-MINIMIS AMOUNTS. AT THE TIME OF CLOSURE, THE DRILL CUTTINGS MUST ALSO MEET THE APPLICABLE STANDARDS OF TABLE 910-1.

(6) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 300 FEET DEEP.

Attachment Check List

Att Doc Num	Name
400315238	FORM 2 SUBMITTED
400315243	30 DAY NOTICE LETTER

Total Attach: 2 Files

General Comments

User Group	Comment	Comment Date
Permit	No LGD or public comments. Built location w/ 2 producing wells and one injection well. Final Review--passed.	9/13/2012 8:48:25 AM
LGD	Passed DB	8/29/2012 11:39:21 AM

Total: 2 comment(s)

BMP

Type	Comment

Total: 0 comment(s)