



Well Name: Williams Production RMT
Well Name: Fed RGU 521-36-198
Pad Name: Fed RGU 24-25-198
Legal Description: SESWSEC25TWP1SRNG98W
Unit: Ryan Gulch
Unit # COC068239
COGCC # 96850
API # 05-103-11873-00
County: Rio Blanco
Field: Sulphur Creek
Field # 80090
Rig Name and Number: CYCLONE 29
Williams Supervisor: Ted Ragsdale
Phone number at rig: 970-988-3854

RECEIVED

SEP 13 2012

COGCC

This notice, sent on	09/13/2012 @ 03:30	is to inform you that Williams
ran and cemented	9-5/8" Surface	casing.
Depth casing landed	3,941'	
Volume pumped	173.38 ,59.34 ,272.28	
Sack of cement used	550 , 170, 780	
Cement density	12.8 , 12.8 , 12.8	
Yield cubic ft/sack	1.77, 1.96, 1.96	
Stages	2	
Lift Pressure	900,556	psi
Bumped plug	YES/ YES	
Bump pressure	1120 / 1750	psi
Floats held	YES / YES	
Returns	FULL / FULL	
Losses	0 / 0	

Additionally:

HOLE SIZE 14-3/4" T/ 1780' & 13-1/2" T/ 3945' / 9-5/8" CSG
40#/FT. & 36#/FT. J-55 SET @ 3,941' FLOAT SHOE & FLOAT
COLLOR USED , STAGE TOOL @ 1,846' / LIFT 1ST STAGE 900
PSI BUMP @ 1120 PSI BHELD 2 MIN FLOATS HELD / 2ND
STAGE LIFT 430 PSI BUMP @ 1750 PSI HELD 2 MIN. STAGE
TOOL CLOSED & HELD / CEMENT T/ SURFACE F/ 1ST STAGE 50
BBLS / 2ND STAGE 40 BBLS / CEMENT FELL 137' TAG 7 PUMP
36 BBLS 15.8 PPG NEAT G-CEMENT TILL CEMENT T/ SURFACE