

Map Unit Description

Lincoln County, Colorado

161 Olnest sandy loam, 1 to 3 percent slopes

Setting

Elevation: 4400 to 6000 feet
Mean annual precipitation: 11 to 16 inches
Mean annual air temperature: 46 to 52 degrees F
Frost-free period: 135 to 155 days

Composition

Olnest and similar soils: 85 percent
Minor components: 15 percent

Description of Olnest

Setting

Landform: Plains
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Eolian deposits

Properties and Qualities

Slope: 1 to 3 percent
Drainage class: Well drained
Capacity of the most limiting layer to transmit water (Ksat): Moderately high or high (0.60 to 2.00 in/hr)
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate maximum: 15 percent
Gypsum maximum: 0 percent
Available water capacity: Moderate (about 8.2 inches)

Interpretive Groups

Land capability (non irrigated): 3e
Ecological site: Sandy Plains (R067BY024CO)

Typical Profile

0 to 8 inches: sandy loam
8 to 38 inches: sandy clay loam
38 to 60 inches: loam

Minor Components

Apishapa soils

Percent of map unit: 5 percent
Landform: Depressions
Ecological site: Plains Swale (R067XY010CO)

Vona soils

Percent of map unit: 5 percent
Landform: Hills
Other vegetative classification: SANDY PLAINS (067XY024CO_1)

Arvada soils

Percent of map unit: 5 percent
Landform: Fans, drainageways
Other vegetative classification: Salt Flat (069AY033CO_1)