



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600508

Date <u>5/24/12</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>32-15</u>	Lease <u>Checketts</u>
County <u>Weld</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (Xtreme #11)</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	Fl.	
<u>Surface</u>	<u>8 5/8" CSG-24"</u>	<u>547</u>	
Plug	Bottom of Surface	Fl.	
		<u>537</u>	
Production	Plug Landed @ <u>493</u>	Fl.	Time On <u>1500</u>
	Pipe Landed @ <u>537</u>	Fl.	Plug Down <u>1830</u>

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>✓ Type III</u>	340	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Crete 1/4 # Per Sack				
Mileage Charge	108	Miles		
Fuel Surcharge	108	Miles		
Additional Cement		SKS		
Mixing Rate 4 BPM	Pre-Flush	1801 - 1806		
Disp. Rate 5 BPM	Mixing	1806 - 1821		
Slurry Vol. 1.32 ³ Cu.FL/Sk	Change Valves	1821 - 1824		
Slurry Wt. 14.8 - 15.0 PPG	Displacement	1824 - 1830		
Water/Cement 6.25 Gal/SK				
Water Temp. 61°F				
Total Slurry Vol. 80	BBLs Cement			
Landed Plug @ 400	PSI/Final Lift @ 200	PSI		
Pre-Flush W/ 20	BBLs H ₂ O	Tax Reference Code	Sub Total	
Displace W/ 31.3	BBLs H ₂ O	State CO 2.9%	Tax	
Circulate 4	BBLs Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1208		Pump Truck		36			
1214		Bulk Truck		36			

We do not assume any responsibility for any damage or conditions resulting from our services. Our pricing is subject to review and revision.

Delivered By Justin Jimenez

Received By [Signature]

Customer or H&B Agent

Duaine Bell

User ID Z0SB4

WBS/NO/CC

G/L Acct 80012090

2043334