

WPX Energy Rocky Mountain, LLC

RGU 332-25-198

Sulphur Creek Field

SHL 2154' FNL 1719' FEL (SW/4 NE/4) BHL 1834' FNL 1910' FEL (SW/4 NE/4)

Section 25-T1S-R98W 6th PM

Garfield County, Colorado

Formation Tops
(Measured Depths)

Mesaverde @ 7910'

Cameo @ 11026'

Rollins @ 11584'

Cozzette @ 11722'

Corcoran @ 11945'

Sego @ 12322'

PBTD @ 12756'

TMD @ 12805'

TVD @ 12790'

Conductor 30" Hole 18" casing/liner 80' W/135 sks cmt

Cmt @ Surface - (Cmt circ to surf during cmt job)

9 5/8" 32.3# ppf Csg. Set @ 3920'
In 14 1/4" Hole W/1790 Sks. Cmt

Top Of Cement 6931'

10006-10191' Mesaverde
10279-10465' Mesaverde
10544-10687' Mesaverde
10756-11022' Mesaverde
11117-11254' Cameo
11299-11507' Cameo
11938-11939' Cozzette
11971-12287' Corcoran
12351-12378' Sego
12407-12595' Sego

4-1/2", 11.6 ppf. Csg. Set @ 12795' W/ 1790 sks Cmt