

FORM  
5A

Rev  
06/12

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400307334

Date Received:

07/23/2012

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 96850  
2. Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC  
3. Address: 1001 17TH STREET - SUITE #1200  
City: DENVER State: CO Zip: 80202  
4. Contact Name: Howard Harris  
Phone: (303) 606-4086  
Fax: (303) 629-8268

5. API Number 05-045-20767-00  
6. County: GARFIELD  
7. Well Name: Hoeppli  
Well Number: RWF 12-36  
8. Location: QtrQtr: SEnw Section: 36 Township: 6S Range: 94W Meridian: 6  
9. Field Name: RULISON Field Code: 75400

### Completed Interval

FORMATION: WILLIAMS FORK-CAMEO COAL Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 04/20/2012 End Date: 04/23/2012 Date of First Production this formation: 04/22/2012

Perforations Top: 6756 Bottom: 8444 No. Holes: 123 Hole size: 35/100

Provide a brief summary of the formation treatment: Open Hole: ☐

2534 Gal 7 1/2% HCL; 17311 BBL Slickwater; 64400# 100 Mesh Snd and 667000#30/50 Mesh Sand (Summary)

All flowback water entries are total estimates based on commingled volumes.

This formation is commingled with another formation: ☐ Yes ☒ No

Total fluid used in treatment (bbl): 17371 Max pressure during treatment (psi): 6969

Total gas used in treatment (mcf): Fluid density at initial fracture (lbs/gal): 8.43

Type of gas used in treatment: Min frac gradient (psi/ft): 0.56

Total acid used in treatment (bbl): 60 Number of staged intervals: 6

Recycled water used in treatment (bbl): 17311 Flowback volume recovered (bbl):

Fresh water used in treatment (bbl): Disposition method for flowback: RECYCLE

Total proppant used (lbs): 731400 Rule 805 green completion techniques were utilized: ☒

Reason why green completion not utilized:

Fracture stimulations must be reported on [FracFocus.org](http://FracFocus.org)

### Test Information:

Date: 05/31/2012 Hours: 24 Bbl oil: 0 Mcf Gas: 1039 Bbl H2O: 0

Calculated 24 hour rate: Bbl oil: 0 Mcf Gas: 1039 Bbl H2O: 0 GOR: 0

Test Method: Flowing Casing PSI: 1661 Tubing PSI: 1394 Choke Size: 20/64

Gas Disposition: SOLD Gas Type: DRY Btu Gas: 1092 API Gravity Oil: 0

Tubing Size: 2 + 3/8 Tubing Setting Depth: 8251 Tbg setting date: 04/26/2012 Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

\*\* Bridge Plug Depth: \*\* Sacks cement on top: \*\* Wireline and Cement Job Summary must be attached.

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: Print Name: Howard Harris

Title: Sr. Regulatory Specialist Date: 7/23/2012 Email: howard.harris@wpenergy.com

### Attachment Check List

Att Doc Num	Name
400307334	FORM 5A SUBMITTED

Total Attach: 1 Files

### General Comments

User Group	Comment	Comment Date
Permit	WBD attached to form 5	9/20/2012 9:26:43 AM

Total: 1 comment(s)