

## WELLBORE DIAGRAM

### Bayswater Exploration NC Farms 20-32

SESE Sec 32 T 7N R 64W

SHL: 185' FSL: & 755' FEL

BHL: 1284' FSL 1292' FEL

Weld County Co

05 123 34793

3rd well head from west of 5 well heads

Directional

Updated

3/1/2012

RO

G.L.= 4804

K.B.= 4820

16

8 5/8 24# sfc csg set @ 817'

Cmt w/ 580 sks

TOC=2150'

<<

>>

**Codell: 7248'-7261', 4 spf**

Frac 3/1/12: 276,302 gals, (179,397 gals SLF), 181,520 lbs 30/50 White

PDTD=7428'

TD= 7463'

4 1/2" 11.6# csg set @ 7446'

Cmt'd w/ 840 sx