

WELLBORE DIAGRAM

Directions: Hwy 85 S to Hwy 7, W to Quebec 1/2 mi N, E & N into

Bayswater Exploration & Prod

Zarlengo 6-4

SENW Section 4-T4N-R67W

SHL: 1938' FNL, 1828' FWL

Updated

8/10/2012

JRR

Adams County CO
05-001-09737

G.L.= 5155
K.B.= 5169
14

8-5/8" set at 1180'
Cmt'd w/ 468 sx to Surf.

TOC: 1456'
CBL

<<

>>

Sussex: 4990'-5004', 5020'-5034', 4 spf

Frac'd 3/21/12 with 30,996 gals, 1,578 MSCF nitrogen, 222,000 lbs 16/30 White Sand, 20,200 lbs 20/40 SLC

PBTD= 5,201'

4-1/2" 11.6# CSG @ 5218' (7-7/8" O.H.)

TD MD= 5,234'

Cmt'd w/ 530 sx

TD VD= 5,234'