

Magna Energy Services, LLC
17509 County Road 14,
Ft. Morgan, Colorado 80701
(970)-867-9007 or (970)-867-8374 (Fax)
Job Log

Date: 8-26-12

Operator: EnCana Oil and Gas
Well name: Bull Fork Unit 3
API #: 05-045-06939-0000
Location: Garfield County, Colorado
Legals: Section 19, 4 South, 97 West
AFE #:

MIRU, Blow down well, NDWH, NUBOP, TOH and tally tubing, PU bit
TIH with bit to 5,627', TOH and LD bit, PU 5-1/2" CIBP, TIH and set at 5,600'
Roll hole with 52 bbl. of production water, Pressure test casing, Pressure held
TIH and Pump 10 sxs (84') of cement on top of CIBP at 5,600'
TOH, RU wireline, TIH and perf at 2,411', TOH, TIH and perf at 100', TOH, RD wireline
TIH to 2,476' and break circulation with 11 bbl. of production water
Pump 40 sxs of cement 3% CaCl, TOH and WOC
TIH and tag TOC at 2,135' (341' plug), TOH, NDBOP, RUWH, Roll hole
TIH with 1" into 5-1/2" casing and pump 30 sxs of cement from 150' to surface
Dig out and cut off well head 4' below ground level
TIH with 1" into annulus and pump 60 sxs to surface, WOC
Top off cement (fell 4'), Welded on information plate onto well, Backfill pit
RDMO

*** All cement is 15.8# Class "G" neat cement, yield 1.15 ***

Cementing contractor: Magna Energy Services, LLC
Cementing contractor supervisor: Daniel Norton
Operator supervisor: Bill Kraft
BLM Representative: Joe Beck
Wireline contractor: Magna Energy Services, LLC