

FORM  
5A

Rev  
06/12

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400330221

Date Received:

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 47120  
2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP  
3. Address: P O BOX 173779  
City: DENVER State: CO Zip: 80217-  
4. Contact Name: JOEL MALEFYT  
Phone: (720) 929-6828  
Fax: (720) 929-7828

5. API Number 05-123-35163-00  
6. County: WELD  
7. Well Name: BROWN  
Well Number: 14N-26HZ  
8. Location: QtrQtr: SWSW Section: 35 Township: 3N Range: 66W Meridian: 6  
9. Field Name: WATTENBERG Field Code: 90750

Completed Interval

FORMATION: NIOBRARA Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 07/16/2012 End Date: 07/18/2012 Date of First Production this formation: 08/06/2012

Perforations Top: 7971 Bottom: 12810 No. Holes: 0 Hole size: 0

Provide a brief summary of the formation treatment: Open Hole: ☒

FRAC'D THROUGH AN OPEN HOLE LINER FROM 7971-12810. AVERAGE TREATING PRESSURE 4926, AVERAGE RATE 58.8. 1928880# 40/70, 301960# 60/50, 24060# 20/40, TOTAL SAND WEIGHT 2254900#

This formation is commingled with another formation: ☐ Yes ☒ No

Total fluid used in treatment (bbl): 93199 Max pressure during treatment (psi): 6880

Total gas used in treatment (mcf): Fluid density at initial fracture (lbs/gal): 8.30

Type of gas used in treatment: Min frac gradient (psi/ft): 0.93

Total acid used in treatment (bbl): Number of staged intervals: 24

Recycled water used in treatment (bbl): Flowback volume recovered (bbl): 10170

Fresh water used in treatment (bbl): 82649 Disposition method for flowback: DISPOSAL

Total proppant used (lbs): 2254900 Rule 805 green completion techniques were utilized: ☒

Reason why green completion not utilized:

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 08/07/2012 Hours: 24 Bbl oil: 292 Mcf Gas: 812 Bbl H2O: 0

Calculated 24 hour rate: Bbl oil: 292 Mcf Gas: 812 Bbl H2O: 0 GOR: 2781

Test Method: FLOWING Casing PSI: 2723 Tubing PSI: 2022 Choke Size: 12/64

Gas Disposition: SOLD Gas Type: WET Btu Gas: 1228 API Gravity Oil: 48

Tubing Size: 2 + 3/8 Tubing Setting Depth: 7384 Tbg setting date: 08/04/2012 Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

\*\* Bridge Plug Depth: \*\* Sacks cement on top: \*\* Wireline and Cement Job Summary must be attached.

Comment:

--

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: JOEL MALEFYT  
Title: REGULATORY ANALYST Date: \_\_\_\_\_ Email JOEL.MALEFYT@ANADARKO.COM  
:

### **Attachment Check List**

Att Doc Num	Name

Total Attach: 0 Files

### **General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>

Total: 0 comment(s)