



Andrews, David

045-15489

**From:** Jeremy Rose [jrose@magnaes.com]  
**Sent:** Saturday, September 22, 2012 4:50 PM  
**To:** Dave Rebol (daverebol@hotmail.com); harlanhodge@hotmail.com;  
steven.vencill@encana.com; Kathy highberger (dkama@kci.net)  
**Cc:** aronrt@hotmail.com; nortonjr69@gmail.com; Longworth, Mike; Andrews, David  
**Subject:** Daily Report for Rig # 8 (2)

**Follow Up Flag:** Follow up  
**Flag Status:** Flagged

DATE: 9/22/2012

**OPERATOR:** EnCana Oil and Gas  
**WELL NAME:** N. Parachute EF07A-20 C29 595  
**COUNTY:** Garfield, Colorado

11:00-12:30 MIRU. Spot in cement equipment.  
12:30-2:00 Trip in hole and tag with joint 89 at 2722'. Shoe is at 2821'. BLM (Dave Andrews) approved us to proceed with original procedure.  
2:00- 3:00 Pump 40 sacks (105') of cement into 9-5/8" casing at 2720'. Clean up cement equipment.  
3:00-4:00 Trip out of hole with 10 joints (310') and secure well site. Shut down for night.  
4:00-5:00 Travel to Parachute, Colorado.

**\*\*All cement pumped was 15.8# Class "G" Neat with a yield of 1.15\*\***

Tool Pusher: Jeremy Rose  
Work Over: Magna Energy Services Rig # 8  
Cement Con. Magna Energy Services  
Cement Sup. Jeremy Rose  
Operations Sup. Steve Vencill  
BLM Representative: Mike Longworth