

FORM  
5A

Rev  
06/12

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400331674

Date Received:

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 96850  
2. Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC  
3. Address: 1001 17TH STREET - SUITE #1200  
City: DENVER State: CO Zip: 80202  
4. Contact Name: Sandra Salazar  
Phone: (303) 629-8456  
Fax: (303) 629-8268

5. API Number 05-045-20456-00  
6. County: GARFIELD  
7. Well Name: Savage Well Number: RWF 441-34  
8. Location: QtrQtr: SWNW Section: 35 Township: 6S Range: 94W Meridian: 6  
9. Field Name: RULISON Field Code: 75400

### Completed Interval

FORMATION: WILLIAMS FORK - CAMEO Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 07/06/2012 End Date: Date of First Production this formation: 07/08/2012

Perforations Top: 5843 Bottom: 7800 No. Holes: 134 Hole size: 0.035

Provide a brief summary of the formation treatment:

Open Hole: ☐

4028 Gals 10% HCL; 357500 # 30/50 Sand; 511500 100 Mesh; 24188 Bbls Slickwater (Summary)

This formation is commingled with another formation: ☐ Yes ☒ No

Total fluid used in treatment (bbl): 24284

Max pressure during treatment (psi):

Total gas used in treatment (mcf):

Fluid density at initial fracture (lbs/gal): 0.80

Type of gas used in treatment:

Min frac gradient (psi/ft): 8.43

Total acid used in treatment (bbl): 95

Number of staged intervals: 6

Recycled water used in treatment (bbl): 24188

Flowback volume recovered (bbl): 1415

Fresh water used in treatment (bbl):

Disposition method for flowback: RECYCLE

Total proppant used (lbs): 869000

Rule 805 green completion techniques were utilized: ☒

Reason why green completion not utilized:

Fracture stimulations must be reported on FracFocus.org

#### Test Information:

Date: 09/15/2012 Hours: 24 Bbl oil: 0 Mcf Gas: 0 Bbl H2O: 0

Calculated 24 hour rate: Bbl oil: 0 Mcf Gas: 928 Bbl H2O: 0 GOR: 0

Test Method: Flowing Casing PSI: 2112 Tubing PSI: 1905 Choke Size: 11/64

Gas Disposition: SOLD Gas Type: DRY Btu Gas: 1092 API Gravity Oil: 0

Tubing Size: 2 + 3/8 Tubing Setting Depth: 7585 Tbg setting date: 07/23/2012 Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

\*\* Bridge Plug Depth: \*\* Sacks cement on top: \*\* Wireline and Cement Job Summary must be attached.

Comment:

- All flowback water entries are total estimates based on commingled volumes.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: Print Name: Sandra Salazar

Title: Permit Technician II Date: Email: sandra.salazar@wpenergy.com

### Attachment Check List

Att Doc Num	Name
400331682	WELLBORE DIAGRAM

Total Attach: 1 Files

### General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)