

FORM
5Rev
02/08

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400332924

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 96850

4. Contact Name: Angela Neifert-Kraiser

2. Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC

Phone: (303) 606-4398

3. Address: 1001 17TH STREET - SUITE #1200

Fax: (303) 629-8268

City: DENVER State: CO Zip: 80202

5. API Number 05-045-20984-00

6. County: GARFIELD

7. Well Name: Jolley

Well Number: KP 524-8

8. Location: QtrQtr: SESW Section: 8 Township: 6S Range: 91W Meridian: 6

Footage at surface: Distance: 188 feet Direction: FSL Distance: 2326 feet Direction: FWL

As Drilled Latitude: 39.535510 As Drilled Longitude: -107.579788

GPS Data:

Date of Measurement: 10/07/2011 PDOP Reading: 2.1 GPS Instrument Operator's Name: Jack Kirkpatrick

** If directional footage at Top of Prod. Zone Dist.: 195 feet. Direction: FSL Dist.: 1930 feet. Direction: FWL

Sec: 8 Twp: 6s Rng: 91w

** If directional footage at Bottom Hole Dist.: 228 feet. Direction: FSL Dist.: 1945 feet. Direction: FWL

Sec: 8 Twp: 6s Rng: 91w

9. Field Name: KOKOPELLI

10. Field Number: 47525

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 03/11/2012 13. Date TD: 03/16/2012 14. Date Casing Set or D&A: 03/17/2012

15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 7283 TVD** 7261 17 Plug Back Total Depth MD 7235 TVD** 7213

18. Elevations GR 6526 KB 6552

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

CBL, Mud, and Reservoir Performance Monitor (RPM)

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	18	48	0	90	34	0	90	VISU
SURF	13+1/2	9+5/8	32.3	0	1,236	355	0	1,236	VISU
1ST	7+7/8	4+1/2	11.6	0	7,267	1,200	4,024	7,267	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
MESAVERDE	3,448		<input type="checkbox"/>	<input type="checkbox"/>	
CAMEO	6,889		<input type="checkbox"/>	<input type="checkbox"/>	
ROLLINS	7,113		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

Please note: the "as-drilled" GPS information provided is actual data of the existing well conductor location prior to the big rig spud date.

*All flowback water entries are total estimates based on comingled volumes.

SISP#0

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Angela Neifert-Kraiser

Title: Regulatory Specialist

Date:

Email: angela.neifert-kraiser@wpenergy.com

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400332931	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400332929	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400332928	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400332935	WELLBORE DIAGRAM	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments**User Group****Comment****Comment Date**

--	--	--

Total: 0 comment(s)