



Andrews, David

045-20995

From: Vallad, Gary [Gary.Vallad@wpenergy.com]
Sent: Tuesday, April 24, 2012 11:39 AM
To: jjking@blm.gov; dgiboo@blm.gov; griosaguilar@blm.gov; Longworth, Mike; Kellerby, Shaun; Andrews, David; Foster, Nicole; Abbey, Jarvis; McAdam, Douglas; Brown, Robert C; Beougher, Justin; Stomley, Leonard
Subject: P&A CEMENT REPORT RIG 574 KP 311-17 KP 24-8 PAD
Attachments: KP 311-17 Notifications_Form.xlsx

P&A WELL WITH WITH CLASS G PLUG CEM. DENSITY 17LB. YIELD .99. WATER 3.77. SAX 50. 8.8BBLs. BTM CMNT 96FT WITH KB26FT. -KB 70 FT. TOP CMNT 66FT WITH KB 26FT. -KB46FT. TOTAL HOLE DEPTH 106 FT WITH 10 FT FISH AT BTM 13.75 BIT PLUS BTM HALF MMTR. RAN 94FT 4 1/2 DRILLPIPE TO TOP OF FISH PUMPED CEMENT @ 2BBLs MIN DISPLACED WITH .8 BBLs WATER. PULLED OUT DP FLUSHED WITH MUD. FULL RETURNS TO SURFACE. NO FLUID DROP. WELDED CAP ON TOP OF CONDUCTOR. TEMP P&A. VERBEL PERMISSION FROM DAVID ANDREWS COGCC. 4/24/12 5:17 PM & BOB HARTMAN BLM 4/24/12/5:18. THANK YOU GARY VALLAD WPX 970-379-1961.