

Andrews, David



From: Jeremy Rose [jrose@magnaes.com]
Sent: Tuesday, October 02, 2012 6:18 PM
To: Dave Rebol (daverebol@hotmail.com); harlanhodge@hotmail.com;
steven.vencill@encana.com; Andrews, David; Kathy highberger (dkama@kci.net)
Cc: aronrt@hotmail.com; nortonjr69@gmail.com; Ryan Ludwar
Subject: Daily Report for Rig # 8

DATE: 10/2/2012

OPERATOR: EnCana Oil and Gas
WELL NAME: N. Parachute WF3D A15 596
API #: 05-045-10606-00
COUNTY: Garfield, Colorado

7:00-9:00 Travel to Parachute, Colorado.
9:00-11:00 Travel to location from Rifle, Colorado. JSA.
11:00-12:30 MIRU. Set up all cement equipment and move in work string.
12:30-2:00 Trip in hole with 78 joints of 2.375" tubing and hard tag at 2392'. Hook up cement equipment.
2:00-3:00 Pump 40 sacks (105') into 9-5/8" casing at 2390'. Displace with 9 barrels. Clean up all cement
equipment.
3:00-4:00 Trip out of hole with 12 joints. Shut well in for night.
4:00-5:00 Travel to Parachute, Colorado.

****All cement pumped was 15.8# Class "G" Neat with a yield of 1.15****

Tool Pusher: Jeremy Rose
Work Over Unit: Magna Energy Services Rig # 8
Cement Contractor: Magna Energy Services
Cement Supervisor: Jeremy Rose
Operations Supervisor: Steve Vencill
BLM Representative: Mike Longworth