



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600450

Date	3-24-12	Well Owner	Kerr McGee	Well No.	4C-34 H2	Lease	RATTLEP
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (MAJOR-42)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Ft.	911		
Surface	9 5/8" CSG-36" - 13 1/2" HWC	Bottom of Surface		Ft.	901		
Plug		Plug Landed @	859	Ft.	Time On	1545	
Production		Pipe Landed @	901	Ft.	Plug Down	1830	

Description	Qty.	Mess.	Unit Price	Amount
Set Up Charge	1			
Cement Nest TYPE III	670	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cete 1/4 # Per Sack				
Mileage Charge	132	Miles		
Fuel Surcharge	132	MILES		
Additional Cement		SKS		
Mixing Rate	4 BPM	Pre-Flush	1727	-1734
Disp. Rate	5 BPM	Mixing	1734	-1814
Slurry Vol.	1.32 ³ Cu.Ft./Sk	Change Valves	1814	-1817
Slurry Wt.	14.8 - 15.0 PPG	Displacement	1817	-1830
Water/Cement	6.25 Gal/SK			
Water Temp.	60°F			
Total Slurry Vol.	157.5	BBLs Cement		
Landed Plug @	800	PSI/Final Lift @	300	PSI
Pre-Flush W/	30	BBLs H ₂ O	Tax Reference Code	Sub Total
Displace W/	66.4	BBLs H ₂ O	State	CO 2.9%
Circulate	5	BBLs Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		44			
1216/1217		Bulk Truck		44/44			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JOE, JOSH Z., CRNIE, JOSH A.

Received By Randy Cusle
Customer or His Agent