



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

601062

Date	9/7/12	Well Owner	Kerr McGee	Well No.	360-1	Lease	PEHR
County	Weld	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (Xtreme #11)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		FL	938		
Surface	8 5/8" 156-24*	Bottom of Surface		FL	928		
Plug		Plug Landed @	884	FL	Time On	2000	
Production		Pipe Landed @	928	FL	Plug Down	2330	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat	580	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cote 1/4 # Per Sack				
Mileage Charge	210	Miles		
Fuel Surcharge	210	Miles		
Additional Cement		SKS		
Mixing Rate	4 BPM	Pre-Flush	2246	2251
Disp. Rate	5 BPM	Mixing	2251	2316
Slurry Vol.	1.32 ³ Cu.Ft./Sk	Change Valves	2316	2319
Slurry Wt.	14.8 - 15.0 PPG	Displacement	2319	2330
Water/Cement	6.25 Gal/SK			
Water Temp.	67°F			
Total Slurry Vol.	136.3	BBLS Cement		
Landed Plug @	200	PSI/Final Lift @	100	PSI
Pre-Flush W/	30	BBLS H ₂ O		
Displace W/	56.2	BBLS H ₂ O		
Circulate	6	BBLS Cement		

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1208		Pump Truck		70			
1207/1214		Bulk Truck		70/70			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin, Evan & Steve

Received By

Craig Jones

Customer or His Agent