



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600330

Date	1/29/12	Well Owner	Kerr McGee	Well No.	38N-26H2	Lease	Camp
County	Weld	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (Major 44)						
City, State Zip	Denver, Colorado 80202						
Type of Job			Depth	Ft. 925			
Surface	9545636" 13 1/2" Hole.		Bottom of Surface	Ft. 914			
Plug			Plug Landed @	875	Ft.	Time On	2245
Production			Pipe Landed @	914	Ft.	Plug Down	0930

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III 100% Excess	680	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Crete 1/4 # Per Sack				
Mileage Charge 2059374	126	Miles		
Fuel Surcharge 8001090	126	miles		
Additional Cement	40	SKS		
Mixing Rate 4 BPM	Pre-Flush 0829	0833		
Disp. Rate 5 BPM	Mixing 0833	0913		
Slurry Vol. 1.32 ³ Cu.Ft./Sk	Change Valves 0913	0916		
Slurry Wt. 14.8 - 15.0 PPG	Displacement 0916	0930		
Water/Cement 6.25 Gal/SK				
Water Temp. 50°F				
Total Slurry Vol. 169.2	BBLS Cement			
Landed Plug @ 525	PSI/Final Lift @ 250	PSI		
Pre-Flush W/ 20	BBLS H ₂ O	Tax Reference Code	Sub Total	
Displace W/ 67.6	BBLS H ₂ O	State CO 2.9%	Tax	
Circulate 4	BBLS Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		42			
1217/1218		Bulk Truck		42/42			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By J. M. Adam, Jason, Kevin

Received By *Randy Case*
Customer or His Agent