

FORM
5A

Rev
06/12

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400330129

Date Received:

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 47120
2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP
3. Address: P O BOX 173779
City: DENVER State: CO Zip: 80217-
4. Contact Name: JOEL MALEFYT
Phone: (720) 929-6828
Fax: (720) 929-7828

5. API Number 05-123-34956-00
6. County: WELD
7. Well Name: CAMP
Well Number: 37N-26HZ
8. Location: QtrQtr: NENE Section: 26 Township: 3N Range: 66W Meridian: 6
9. Field Name: WATTENBERG Field Code: 90750

Completed Interval

FORMATION: NIOBRARA Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 06/16/2012 End Date: 06/18/2012 Date of First Production this formation: 07/05/2012

Perforations Top: 7769 Bottom: 11779 No. Holes: 0 Hole size: 0

Provide a brief summary of the formation treatment: Open Hole: ☒

FRAC'D THROUGH AN OPEN HOLE LINER FROM 7769-11779. AVERAGE TREATING PRESSURE 5136, AVERAGE RATE 56. 1020480# 40/70, 2261780# 30/50, 138400# SB EXCEL, TOTAL SAND WEIGHT 3420660#.

This formation is commingled with another formation: ☐ Yes ☒ No

Total fluid used in treatment (bbl): 71141 Max pressure during treatment (psi): 7608

Total gas used in treatment (mcf): Fluid density at initial fracture (lbs/gal): 8.30

Type of gas used in treatment: Min frac gradient (psi/ft): 0.90

Total acid used in treatment (bbl): Number of staged intervals: 19

Recycled water used in treatment (bbl): Flowback volume recovered (bbl): 7252

Fresh water used in treatment (bbl): 35815 Disposition method for flowback: DISPOSAL

Total proppant used (lbs): 3420660 Rule 805 green completion techniques were utilized: ☒

Reason why green completion not utilized:

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 07/12/2012 Hours: 24 Bbl oil: 200 Mcf Gas: 700 Bbl H2O: 0

Calculated 24 hour rate: Bbl oil: 200 Mcf Gas: 700 Bbl H2O: 0 GOR: 3500

Test Method: FLOWING Casing PSI: 2815 Tubing PSI: 2086 Choke Size: 12/64

Gas Disposition: SOLD Gas Type: WET Btu Gas: 1227 API Gravity Oil: 52

Tubing Size: 2 + 3/8 Tubing Setting Depth: 7236 Tbg setting date: 06/30/2012 Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

** Bridge Plug Depth: ** Sacks cement on top: ** Wireline and Cement Job Summary must be attached.

Comment:

--

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: JOEL MALEFYT

Title: REGULATORY ANALYST

Date: _____

Email JOEL.MALEFYT@ANADARKO.COM

:

Attachment Check List

Att Doc Num	Name

Total Attach: 0 Files

General Comments

User Group

Comment

Comment Date

--	--	--

Total: 0 comment(s)