

FORM

2

Rev  
12/05

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400325244

Date Received:

09/11/2012

## APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

## 2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
 SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☒Sidetrack ☐

PluggingBond SuretyID

20040105

3. Name of Operator: BERRY PETROLEUM COMPANY

4. COGCC Operator Number: 10091

5. Address: 1999 BROADWAY STE 3700

City: DENVER State: CO Zip: 80202

6. Contact Name: HEIDI BANG Phone: (303)999-4262 Fax: (303)999-4362

Email: HSB@BRY.COM

7. Well Name: OXY Well Number: 21-2D

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 9026

## WELL LOCATION INFORMATION

10. QtrQtr: NESE Sec: 21 Twp: 6S Rng: 97W Meridian: 6

Latitude: 39.506178 Longitude: -108.217269

Footage at Surface: 1800 feet FNL/FSL 518 feet FEL/FWL  
 FSL FEL

11. Field Name: GRAND VALLEY Field Number: 31290

12. Ground Elevation: 8366 13. County: GARFIELD

## 14. GPS Data:

Date of Measurement: 01/29/2007 PDOP Reading: 3.7 Instrument Operator's Name: ROBERT KAY

15. If well is ☒ Directional ☐ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL  
 522 FSL 529 FEL 522 FSL 529 FEL  
 Sec: 21 Twp: 6S Rng: 97W Sec: 21 Twp: 6S Rng: 97W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 3590 ft

18. Distance to nearest property line: 1987 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 332 ft

## 20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
WILLIAMS FORK	WMFK	510-18	320	S2

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#:23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

SURFACE USE AGREEMENT AND MINERAL LEASE MAP ATTACHED TO ORIGINAL APD.

25. Distance to Nearest Mineral Lease Line: 529 ft

26. Total Acres in Lease: 5165

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	30	20	55	0	90	100	90	0
SURF	16	9+5/8	36	0	2,000	1,000	2,000	0
1ST	8+3/4	4+1/2	11.6	0	9,026	600	9,026	200

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments I certify that there have been no changes on land use, lease description. The pad has been built. The pit has been constructed. The location does not require a variance from any of the rules listed in Rule 306.d.(1).(A).(ii). The location is not in a wildlife restricted surface occupancy area. This location is not in a wildlife sensitive habitat area. No rig on site. The production cement top will be > 200' above the top of gas. Oxy owns surface and Chevron owns minerals.

34. Location ID: 416468

35. Is this application in a Comprehensive Drilling Plan? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment? ☐ Yes ☒ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: HEIDI BANG

Title: REG COMPLIANCE ASST

Date: 9/11/2012

Email: HSB@BRY.COM

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_

Director of COGCC

Date: 10/3/2012

#### API NUMBER

05 045 19275 00

Permit Number: \_\_\_\_\_ Expiration Date: 10/2/2014

#### CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- (1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.
- (2) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE GARFIELD COUNTY RULISON-FIELD NOTICE TO OPERATORS IS REQUIRED.
- (3) COMPLY WITH ALL PROVISIONS OF THE JUNE 12, 2008 NOTICE TO OPERATORS DRILLING WELLS WITHIN ¾ MILE OF THE RIM OF THE ROAN PLATEAU IN GARFIELD COUNTY -- PIT DESIGN, CONSTRUCTION, AND MONITORING REQUIREMENTS. SEE ATTACHED NOTICE.
- (4) THE NEARBY HILLSIDE MUST BE MONITORED FOR ANY DAY-LIGHTING DRILLING FLUIDS THROUGHOUT THE DRILLING OF THE SURFACE-CASING INTERVAL.
- (5) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 00 FEET DEEP.

### **Attachment Check List**

Att Doc Num	Name
400325244	FORM 2 SUBMITTED

Total Attach: 1 Files

### **General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>
Permit	No LGD or public comments. Final Review--passed.	10/2/2012 8:39:54 AM
Permit	SUA and lease map in well file. Corrected #22a to "NONE". Added S2 for unit configuration. Location has been built, possible interim reclamation issues to be addressed by COGCC reclamation specialists. Added to inactive built location spreadsheet.	9/25/2012 2:46:17 PM
LGD	Passed DB	9/13/2012 8:40:49 AM
Permit	FYI: SHL values do not match well location plat submitted with original APD (SHL on plat read 575' FEL/1889' FSL)	9/11/2012 5:14:26 PM
Permit	Oper. email requested deletion of this sentence: "The location will require surface disturbance of the pad." in the comments field 33. under Drilling Plans and Procedures.	9/11/2012 5:09:17 PM

Total: 5 comment(s)

### **BMP**

<b><u>Type</u></b>	<b><u>Comment</u></b>

Total: 0 comment(s)