

FORM
5Rev
02/08

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

2517491

Date Received:

06/28/2012

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 16700

4. Contact Name: DIANE PETERSON

2. Name of Operator: CHEVRON USA INC

Phone: (970) 675-3842

3. Address: 6001 BOLLINGER CANYON RD

Fax: (970) 675-3800

City: SAN RAMON State: CA Zip: 94583

5. API Number 05-103-11011-00

6. County: RIO BLANCO

7. Well Name: FEE

Well Number: 159X

8. Location: QtrQtr: NWSW Section: 17 Township: 2N Range: 102W Meridian: 6

Footage at surface: Distance: 2428 feet Direction: FSL Distance: 1253 feet Direction: FWL

As Drilled Latitude: 40.142449 As Drilled Longitude: -108.872210

GPS Data:

Data of Measurement: 12/01/2008 PDOP Reading: 2.6 GPS Instrument Operator's Name: JOHN FLOYD W/UELS

** If directional footage at Top of Prod. Zone Dist.: 2482 feet. Direction: FSL Dist.: 1367 feet. Direction: FWL

Sec: 17 Twp: 2N Rng: 102W

** If directional footage at Bottom Hole Dist.: 2355 feet. Direction: FSL Dist.: 1357 feet. Direction: FWL

Sec: 17 Twp: 2N Rng: 102W

9. Field Name: RANGELY

10. Field Number: 72370

11. Federal, Indian or State Lease Number: FEE

12. Spud Date: (when the 1st bit hit the dirt) 02/07/2008 13. Date TD: 08/25/2008 14. Date Casing Set or D&A: 08/22/2008

15. Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 6515 TVD** 6506 17 Plug Back Total Depth MD 6515 TVD** 6506

18. Elevations GR 5333 KB 5355

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

COMPENSATED PHOTO DENSITY, DUAL NEUTRON/ARRAY INDUCTION/TRIPLE COMBO

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	20			0	40		0		
SURF	12+1/4	9+5/8		0	2,012	850	0	2,012	CALC
1ST	8+1/2	7		0	6,342	645	2,050	6,342	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work: _____

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
DAKOTA	3,400		<input type="checkbox"/>	<input type="checkbox"/>	
MORRISON	3,763		<input type="checkbox"/>	<input type="checkbox"/>	
CURTIS	4,528		<input type="checkbox"/>	<input type="checkbox"/>	
ENTRADA	4,623		<input type="checkbox"/>	<input type="checkbox"/>	
CARMEL	4,748		<input type="checkbox"/>	<input type="checkbox"/>	
NAVAJO	4,793		<input type="checkbox"/>	<input type="checkbox"/>	
CHINLE	5,413		<input type="checkbox"/>	<input type="checkbox"/>	
SHINARUMP	5,533		<input type="checkbox"/>	<input type="checkbox"/>	
MOENKOPI	5,631		<input type="checkbox"/>	<input type="checkbox"/>	
WEBER	6,271		<input type="checkbox"/>	<input type="checkbox"/>	

Comment: _____

FORM 5A DOC # 2517495

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: DIANE L. PETERSON

Title: REGULATORY SPECIALIST Date: 1/22/2009 Email: DLPE@CHEVRON.COM

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
2517494	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
2517492	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
2517493	Other	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
<u>Other Attachments</u>					
2517491	FORM 5 SUBMITTED	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	9/10/12 SCB/GR/CCL 1600180 in scanning.	9/14/2012 11:05:00 AM
Permit	8/13/12 CPD/CDN 1599610 CTC/QL 1599609 AI/SF/EL 1599608 in scanning. No CBL run? On hold pending CBL	8/23/2012 2:46:54 PM
Permit	Need paper logs & digital logs.	8/9/2012 10:25:07 AM
Data Entry	CHECK DRILLED LONGITUDE ENTRY.	6/28/2012 11:10:43 AM

Total: 4 comment(s)