

FORM
5

Rev
02/08

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400332950

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 96340

4. Contact Name: Jack Fincham

2. Name of Operator: WIEPKING-FULLERTON ENERGY LLC

Phone: (303) 906-3335

3. Address: 4600 S DOWNING ST

Fax: (303) 761-9067

City: ENGLEWOOD State: CO Zip: 80113

5. API Number 05-073-06466-00

6. County: LINCOLN

7. Well Name: Napali

Well Number: # 5

8. Location: QtrQtr: NWSE Section: 17 Township: 10S Range: 55W Meridian: 6

Footage at surface: Distance: 1980 feet Direction: FSL Distance: 1980 feet Direction: FEL

As Drilled Latitude: 39.176870 As Drilled Longitude: -103.572910

GPS Data:

Data of Measurement: 05/04/2012 PDOP Reading: 2.4 GPS Instrument Operator's Name: Keith Westfall

** If directional footage at Top of Prod. Zone Dist.: feet. Direction: Dist.: feet. Direction:

Sec: Twp: Rng:

** If directional footage at Bottom Hole Dist.: feet. Direction: Dist.: feet. Direction:

Sec: Twp: Rng:

9. Field Name: GREAT PLAINS

10. Field Number: 32756

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 04/14/2012 13. Date TD: 04/27/2012 14. Date Casing Set or D&A: 04/29/2012

15. Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 7900 TVD** 17 Plug Back Total Depth MD 7848 TVD**

18. Elevations GR 5174 KB 5187

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

Compensated Density Compensated Neutron Gamma Ray
High Resolution Induction
Dual Spaced Cement Bond Log

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	17+1/2	13+3/8	48	0	60	100	0	60	VISU
SURF	12+1/4	8+5/8	24	0	298	160	0	298	VISU
1ST	7+7/8	5+1/2	17	0	7,895	280	5,950	7,895	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: 05/07/2012

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom
STAGE TOOL	1ST	4,560	250	2,850	4,560

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
DAKOTA	4,043		<input type="checkbox"/>	<input type="checkbox"/>	
SHAWNEE	6,366		<input type="checkbox"/>	<input type="checkbox"/>	
LANSING	6,592		<input type="checkbox"/>	<input type="checkbox"/>	
MARMATON	6,953		<input type="checkbox"/>	<input type="checkbox"/>	
CHEROKEE	7,064		<input type="checkbox"/>	<input type="checkbox"/>	
ATOKA	7,259		<input type="checkbox"/>	<input type="checkbox"/>	
KEYES	7,759		<input type="checkbox"/>	<input type="checkbox"/>	
MORROW	7,780		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Jack Fincham

Title: Agent Date: _____ Email: fincham4@msn.com

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400333093	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Directional Survey **	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400333095	Other	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
<u>Other Attachments</u>					
400333090	LAS-DENSITY/NEUTRON	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400333116	WELLBORE DIAGRAM	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400333418	PDF-CEMENT BOND	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

User Group

Comment

Comment Date

--	--	--

Total: 0 comment(s)