



FIELD TICKET & TREATMENT REPORT CEMENT

TICKET NUMBER 34411

LOCATION Oakley KS

FOREMAN Kelly Gabel

Walt Dinkel

6/10

620-431-9210 or 800-467-8676

CEMENT

DATE

CUSTOMER #

WELL NAME & NUMBER

SECTION

TOWNSHIP

RANGE

COUNTY

3-5-12

9160

Napali #5

17

10^S

55^W

Lincoln

CUSTOMER

MAILING ADDRESS

CITY

STATE

ZIP CODE

Whipping Fullerton

Limon Colo

415

2nd

E into

TRUCK #

DRIVER

TRUCK #

DRIVER

399

Damon

528

Bobby S

Wes F

8518 241 #

JOB TYPE <u>Surface</u>	HOI.E SIZE <u>12 1/4</u>	HOLE DEPTH <u>298</u>	CASING SIZE & WEIGHT <u>8 5/8 24#</u>
CASING DEPTH <u>298</u>	DRILL PIPE _____	TUBING _____	OTHER _____
SLURRY WEIGHT <u>148</u>	SLURRY VOL _____	WATER gal/sk _____	CEMENT LEFT in CASING <u>20'</u>
DISPLACEMENT <u>17 1/2</u>	DISPLACEMENT PSI _____	MIX PSI _____	RATE _____
REMARKS: <u>safety meeting, Rigged up on well, hooked up to circulate, mixed 160 SKS com 3% occ + 2% gel, shut down, displaced plug with 17 1/2 bbl water, shut in, washed out pumps & lines.</u>			

Approx 4 bbl + 0 pit

Cement did circulate
Thank You
Walt Kelly & crew

[illegible]

Rayin 3737

8:00 PM

AUTHORIZTION

TITLE

DATE 7-7-2012

... or in the customer'

AUTHORIZATION _____
I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form



CONSOLIDATED
Oil Well Services, LLC

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT
CEMENT

TICKET NUMBER 34443
LOCATION Oakley, KS
FOREMAN Kelly Gape
Walt Dinkel

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
4-29-12	9160	Napoli #5	17	105	55W	Lincoln
CUSTOMER <u>Wierking Fullerton</u>			Limon COLO 55 E-MO			
MAILING ADDRESS			TRUCK #	DRIVER	TRUCK #	DRIVER
			4156-T119	Damon M		
			4166-T129	Miles S		
CITY	STATE	ZIP CODE				

JOB TYPE Prod HOLE SIZE 7 7/8 HOLE DEPTH 7900' CASING SIZE & WEIGHT 5 1/2 17 #
CASING DEPTH 7895' DRILL PIPE TUBING OTHER RTG @ 41566
SLURRY WEIGHT 14 SLURRY VOL WATER gal/ek CEMENT LEFT in CASING 40"
DISPLACEMENT 182 1/4 DISPLACEMENT PSI MIX PSI RATE 6-7 bpm

REMARKS: Safety Meeting, rigged up on Muffin drilling rig #25,
ran float equip. Turbos on ITS #2, 3, 4, 5, 17, 18, 19, 20, 21, 23, 24, 25
reg. centralizer on ITS #2, #4 Basket #2, #2 RTG #3, ran 100 ITS & circulated 1/2 hr
ran pipe to bottom. circulated. Pumped 5 bbl water 500 gal mud flush, 5 bbl water
mix 5 SKS in RT, 5 SKS in MT, mixed 280 SKS class H cement, 5" Kol-seal, 29 gal
Clear pump lines, released plug displaced with 181 bbl water @ 1200'
Plug landed @ 1800', released pressure float held, washed out pumps
& lines, rigged down.

Thank You
Walt, Kelly & crew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401P	1	PUMP CHARGE	4050.00	4050.00
5406	100	MILEAGE	5.00	500.00
1115A	290 SKS	class H cement	19.32	5597.00
1111	1377 #	5 gal	.45	619.65
1110A	1450 #	Kol-seal	1.56	812.00
1118B	545 #	Bentonite	.25	136.25
1107	73 #	Flo-seal	2.83	205.86
1144G	500 gal	Mud flush	1.00	500.00
54107A	13.63	Ton mileage delivery	16.7	2276.00
41159	1	AFU Float shoe 5 1/2	4113.00	4113.00
41154	1	5 1/2 Latch down ass.	303.00	303.00
41136	12	Turbo Centralizers 5 1/2	22.00	914.00
41130	2	Centralizer 5 1/2	57.00	116.00
41104	2	5 1/2 Basket 5 1/2	27.00	55.20
41285	1	5 1/2 Port collar	2075.00	2075.00
				19,019.76
				1901.92
				17117.78
		SALES TAX		856.01
		ESTIMATED TOTAL		17973.79

Rev 3737

11:30 PM [Signature]

249432

AUTHORIZATION [Signature] TITLE CO-MAN

DATE 4-29-12

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.



FIELD TICKET & TREATMENT REPORT CEMENT

TICKET NUMBER 34507
LOCATION Oakley Ks
FOREMAN Walt Dinkel

DATE	CUSTOMER #	WELL NAME & NUMBER		SECTION	TOWNSHIP	RANGE	COUNTY
5-7-12	9160	Napali #5		17	10S	55W	Lincoln
CUSTOMER		Wiepking - Fullerton Limon 55		TRUCK #	DRIVER	TRUCK #	DRIVER
MAILING ADDRESS				456-T118	Miles Shaw		
				466-T129	Cody Rector		
CITY		STATE	ZIP CODE				

JOB TYPE <u>Port Collar</u>	HOLE SIZE _____	HOLE DEPTH _____	CASING SIZE & WEIGHT <u>5 1/2"</u>
CASING DEPTH _____	DRILL PIPE _____	TUBING <u>2 3/8"</u>	OTHER <u>PC. 4560'</u>
SLURRY WEIGHT _____	SLURRY VOL _____	WATER gal/sk _____	CEMENT LEFT in CASING _____
DISPLACEMENT <u>25 1/2</u>	DISPLACEMENT PSI _____	MIX PSI _____	RATE _____

REMARKS: Safety mooring, Test Casing to 1500#, Held, open Tool, pump into
 @ 3 1/2 BPM @ 800#, mixed 250 Sls 60% PO2, 6% Gal, 5# Kolseal, 1/4# F/O-Seal
 Displace 25 1/2 BBL H2O @ 1200#, shut tool, Test to 1500#, Held
 ran 6 ITS, Circ Clean

Thank You
Walt & crew

[illegible]

Bavin 3737

AUTHORIZATION

TITLE

DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.