

Berry Petroleum Company
 Berry 1-17D
 API # 05-045-14626-0000
 SENW Sec 01 Twn 6S Rng 97W
 Garfield County, Colorado

Prepared Charles Durkoop
 Updated 11/22/2010

P&A cmt plug @ 30-180', 200 sx Type III @ 14.5 ppg & 1.39 yld
 20" Conductor @ 120'

Rig Frontier 9

P&A cmt plug @ 1700-2000', 386 sx Type III @ 14.4 ppg & 1.41 yld

8339 KB

8311 GL

28 KB-GL

TOF @ 2107'

BHT

16" hole @ 2332'

3/14/2008 Spud
 3/18/2007 Stuck BHA
 3/22/2008 Perf DC
 3/23/2007 Pump P&A Cmt
 3/23/2008 P & A lead and tail

Fish in Hole	Qty	Length	Depth
Top of Fish		2107.00	2107.00
6-1/4" Drill Collar, Perf'd 2112-16', 12 holes		32.27	2139.27
7.8" XO Sub		1.69	2140.96
2-8" Drill Collars, Perf'd 2190-95', 16 holes		61.65	2202.61
8-3/16" Shock Sub		10.37	2212.98
8" NMDC		30.64	2243.62
7-3/4" Emmmitter Sub		10.97	2254.59
8" Tool Carrier		19.60	2274.19
8" Double Pin Sub		2.32	2276.51
7-3/4" UBHO Sub		3.18	2279.69
13-1/4" Mud Motor		30.83	2310.52
16" Tri-Cone Bit		1	2311.52