

## Cement Report

[illegible]

Reger Parson  
Customer Representative

James Romo  
Station Manager

Chad Hirt  
Cement



Customer <i>Cholla Production</i>		Lease No.		Date <i>5-24-12</i>	
Lease <i>Baldwin</i>		Well # <i>2-18</i>		Service Receipt <i>02338</i>	
Casing <i>8 5/8</i>	Depth <i>1759</i>	County <i>BACA</i>		State <i>CO</i>	
Job Type <i>242 Surface</i>		Formation		Legal Description <i>18-32-44</i>	

Pipe Data		Perforating Data		Cement Data
Casing size <i>8 5/8 24#</i>	Tubing Size	Shots/Ft		Lead <i>525sk A-Con</i>
Depth <i>1762</i>	Depth	From	To	<i>2.45ft 2sk 13knd</i>
Volume <i>109</i>	Volume	From	To	<i>18.16sk 11.4#'</i>
Max Press <i>1500</i>	Max Press	From	To	Tail in <i>50sk Class C</i>
Well Connection <i>8 5/8</i>	Annulus Vol.	From	To	<i>1.34ft 2sk</i>
Plug Depth <i>1717</i>	Packer Depth	From	To	<i>4.33sk 14.8#</i>

Time	Casing Pressure	Tubing Pressure	Bbls. Pumped	Rate	Service Log
<i>1015</i>					<i>Arrive On Location</i>
<i>1030</i>					<i>Safety Meeting - Rig Up</i>
<i>1000</i>					<i>Rig Running Casing</i>
<i>1200</i>					<i>No Circulating</i>
<i>1510</i>					<i>Pressure Test</i>
<i>1520</i>	<i>200</i>		<i>210</i>	<i>4.0</i>	<i>Pump Lead cmt @ 11.4# Injected</i>
					<i>Foamer @ 3gpm Start N2 @</i>
					<i>100 SCF6P</i>
<i>1615</i>	<i>250</i>		<i>36</i>	<i>4.0</i>	<i>Pump Tail cmt @ 14.8#</i>
<i>1625</i>					<i>Drop Plug - Wash Up</i>
<i>1630</i>	<i>200</i>		<i>99</i>	<i>4.0</i>	<i>Displace</i>
<i>1655</i>	<i>200</i>		<i>10</i>	<i>2.0</i>	<i>Slow Down - Displace</i>
<i>1700</i>	<i>700</i>		<i>1</i>	<i>1</i>	<i>Land Plug - Float Held</i>
					<i>Put in 325' of one inch pipe</i>
<i>100</i>		<i>400</i>	<i>42</i>	<i>2.5</i>	<i>Pump 125sk of A-Con cmt @ 12.7#</i>
<i>120</i>		<i>400</i>	<i>42</i>	<i>2.5</i>	<i>Pump 175sk of Class C cmt @ 14.8#</i>
<i>130</i>					<i>Cement To Surface</i>
<i>245</i>					<i>Job Complete</i>
					<i>Thanks For Using Basic Energy Services</i>
Service Units	<i>19820</i>	<i>1435-14284</i>	<i>27462</i>	<i>38750-37725</i>	
Driver Names	<i>I Chavez</i>	<i>Victor</i>	<i>Saul</i>	<i>Ramon</i>	

*Roger*  
Customer Representative

*Ben Bentt*  
Station Manager

*James Chavez*  
Cementer



## Cement Report

[illegible]

Customer Representative

Station Manager

Cementer

Taylor Printing, Inc.