

**Magna Energy Services, LLC**  
**17509 County Road 14,**  
**Ft. Morgan, Colorado 80701**  
**(970)-867-9007 or (970)-867-8374 (Fax)**  
**Job Log**

Date: 9-23-12

Operator: EnCana Oil and Gas  
Well name: North Parachute EF11D-20 C29 595  
Location: Garfield County, Colorado  
Legals: NENW, Section 29, 5 South, 95 West  
AFE #:

MIRU, TIH and tag at 2,717', (Shoe at 2,815')  
Pump 40 sxs of cement into 9-5/8" casing, TOH and WOC  
TIH and tag TOC at 2,603', TOH to 120'  
Pump 42 sxs into 9-5/8" casing, Pump 20 sxs into mouse hole  
Hydro Vac. Concrete and rock to 6' below ground level  
Cut casing, welded info cap on well, Backfilled pits, Cleaned location  
RDMO

\*\*\* All cement is 15.8# Class "G" neat cement, yield 1.15 \*\*\*

Cementing contractor: Magna Energy Services, LLC  
Cementing contractor supervisor: Jeremy Rose  
Operator supervisor: Steve Vencill  
COGCC Representative: Mike Longworth  
Wireline contractor: None