

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400331677

Date Received:

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

PluggingBond SuretyID

20120033

3. Name of Operator: ENDEAVOUR OPERATING CORPORATION

4. COGCC Operator Number: 10411

5. Address: 1125 17TH STREET #1525

City: DENVER State: CO Zip: 80202

6. Contact Name: Terry Hoffman Phone: (970)542-8287 Fax: ()

Email: terry@rockymountainpermitting.com

7. Well Name: Wiley Well Number: 23-3-97-1

8. Unit Name (if appl): Wiley Unit Unit Number: COC75390X

9. Proposed Total Measured Depth: 11420

WELL LOCATION INFORMATION

10. QtrQtr: SESE Sec: 23 Twp: 3N Rng: 97W Meridian: 6

Latitude: 40.208891 Longitude: -108.239501

Footage at Surface: 624 feet FNL/FSL 961 feet FEL/FWL FEL

11. Field Name: Wildcat Field Number: 99999

12. Ground Elevation: 6013.5 13. County: RIO BLANCO

14. GPS Data:

Date of Measurement: 08/28/2012 PDOP Reading: 1.5 Instrument Operator's Name: K. Stewart

15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL _____ FEL/FWL _____ Bottom Hole: FNL/FSL _____ FEL/FWL _____

Sec: _____ Twp: _____ Rng: _____ Sec: _____ Twp: _____ Rng: _____

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 5280 ft

18. Distance to nearest property line: 1796 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 5280 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Frontier	FTRR			
Niobrara	NBRR			

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 20120034

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
See attached "lease description"

25. Distance to Nearest Mineral Lease Line: 697 26. Total Acres in Lease: 3757

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☐ Offsite ☒ Onsite **If 28, 29, or 30 are "Yes" a pit permit may be required.**

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	20	16	75	0	80	75	80	0
SURF	14+3/4	9+5/8	36	0	3,000	894	3,000	0
OPEN HOLE	8+3/4			3000	11,420			

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments Footages listed as 5280' are greater than one (1) mile. Set conductor @ 80', 9-5/8" csg @ 3000'. Drill a 8-3/4 to 11420', log well & plug back. Parasite string to be run with 9-5/8 to control "loss circulation." Distance from unit boundary is greater than 600'. This well is being drilled primarily as a "Pilot Hole" (with the potential to produce). Possible lateral to be permitted in the future.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Terry L. Hoffman

Title: Permit Agent Date: _____ Email: terry@rockymountainpermitting.

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Attachment Check List

Att Doc Num	Name
400332994	30 DAY NOTICE LETTER
400333002	LEGAL/LEASE DESCRIPTION
400333246	PLAT

Total Attach: 3 Files

General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)

BMP

Type	Comment
Storm Water/Erosion Control	<p>Endeavour Operating Corporation Wiley #23-3-97-1 NWSE Section 23-T3N-R97W Rio Blanco Co., Colorado</p> <p>Best Management Practices Summary</p> <p>Stormwater Management Plans (SWMP) will be in place to address construction, drilling and operations associated with Oil & Gas development throughout the state of Colorado in accordance with Colorado Department of Public Health and Environment (CDPHE). BMP's will be constructed around the perimeter of the site prior to, or at the beginning of construction. The BMP's used will vary according to the location, and will remain in place until the pad reaches final reclamation.</p> <p>Spill Prevention Control and Counter measures (SPCC) plans will be in place to address any possible spills associated with Oil & Gas operations throughout the state of Colorado in accordance with CFR12.</p> <p>Housekeeping will consist of neat and orderly storage of materials and fluids. Wastes will be temporarily stored in sealed containers and regularly collected and disposed of at offsite, suitable facilities. If spills occur prompt cleanup will be required to minimize any commingling of waste materials with stormwater runoff. Routine maintenance will be limited to fueling and lubrication of equipment. Drip pans will be used during routine fueling and maintenance to contain spills or leaks. Any waste product from maintenance will be containerized and transported offsite for disposal or recycling. There will be no major equipment overhauls conducted onsite. Equipment will be transported offsite for major overhauls. Cleanup will consist of patrolling the roadways, access areas, and other work areas to pick up trash, scrap debris, other discarded materials, and any contaminated soil. These materials will be disposed of properly.</p> <p>The above BMP's will be provided to all Endeavour Operating Corporation, contractors and will be posted in the company trailer located on location during drilling, completion and production operations.</p>

Total: 1 comment(s)