

Berry Petroleum Company  
Chevron 33-17D  
API # 05-045-15287-0000  
SWNW Sec 33 Twn 5S Rng 96W  
Garfield County, Colorado

Prepared Kelly Ramirez  
Updated 10/9/2012

8224 KB  
8196 GL  
28 KB-GL

248 BHT

Csg Holes @ 2602'-3082'

nt Csg Patch @ 3051-91', 3.700" ID

TOC @ 3900'

Marker Jts @  
4778 - 4800' & 7307 - 7330'

20" Conductor @ 120'

16" hole @ 2245'  
51 jts 9-5/8" 36# J-55 surf csg @ 2215' w/ PS, inj port @ 2039'  
cmt 1138 sx Type III lead @ 11.6 ppg & 100 sx Type III tail @ 14.2 ppg

Cmt Sqz 160 sx Class G 15.8 ppg 5/3/10  
Cmt Sqz 150 sx Class G 15.8 ppg 5/5/10  
Sqz Perfs @ 2702' 5/6/210  
Cmt Sqz 100 sx Class G 12.5 ppg & 100 sx 15.8 ppg 5/8/10  
Cmt Sqz 4 bbl Class G 15.8 ppg 5/13/10  
Cmt Sqz 100 sx Class G 15.8 ppg 5/19/10  
Sqz Cmt @ 2538 - 3096', CBL 5/21/10

Equipment in Hole	Qty	Length	Depth
KB		22.00	22.00
NONE			22.00
			22.00
			22.00

2 sx cmt @ 9827'  
CIBP @ 9839'

8-3/4" hole @ 7179' & 7-7/8" hole @ 10126'  
231 jts 4-1/2" 11.6# NS-110 & I-100 prod csg @ 9939', FC @ 9892'  
cmt 630 sx Type III @ 12.5 ppg, 2.69 yield

Fish left in Hole: TOF @ 9991', 7-7/8" bit, mud motor, XO sub, MWD tool, Emitter, NMDC, 1 Jt 4-1/2" HW, 1 partial 4-1/2" HW