




Well Name: WPX Energy RMT.
Well Name: Fed RGU 33-36-198
Pad Name: Fed RGU 33-36-198
Legal Description: NWSESEC36TWP1SRNG98W
Unit: Ryan Gulch
Unit # COC068239X
COGCC # 96850
API # 05-103-11930-00
County: Rio Blanco
Field: Sulphur Creek
Field # 80090
Rig Name and Number: CYCLONE 29
Williams Supervisor: Ted Ragsdale
Phone number at rig: 970-988-3854



| | | |
|----------------------|------------------------|--------------------------------|
| This notice, sent on | 10/07/2012 @15:30 | is to inform you that William: |
| ran and cemented | 9-5/8" Surface | casing. |
| Depth casing landed | 3674' | |
| Volume pumped | 193.87,64.57,326.38,17 | |
| Sack of cement used | 615, 185, 935, 83 | |
| Cement density | 12.8, 12.8, 12.8, 15.8 | |
| Yield cubic ft/sack | 1.77, 1.96, 1.96, 1.15 | |
| Stages | 2 | |
| Lift Pressure | 980, 450, | psi |
| Bumped plug | YES, YES | |
| Bump pressure | 1260, 1650 | psi |
| Floats held | YES, YES | |
| Returns | FULL , FULL | |
| Losses | 0 / 0 | |

Additionally:

FULL RETURNS BOTH STAGES ,60 BBLS CEMENT BACK F/
1ST STAGE , 133 BBLS CEMENT BACK F/ 2ND STAGE,
CEMENT FELL 40' INSIDE CONDUCTOR CASING PUMP 17
BBLS / 83 SACKS 15.8 PPG NEAT G CEMENT TILL CEMENT
BACK T/ SURFACE 7 CEMENT STAYED @ SURFACE