

FORM 5A Rev 06/12

State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Table with columns DE, ET, OE, ES

Document Number: 400335125

Date Received:

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 16700
2. Name of Operator: CHEVRON USA INC
3. Address: 6001 BOLLINGER CANYON RD
City: SAN RAMON State: CA Zip: 94583
4. Contact Name: Julie Justus
Phone: (970) 257-6042
Fax: (970) 245-6393

5. API Number 05-045-18439-00
6. County: GARFIELD
7. Well Name: SKR-698-09-AV
Well Number: 23
8. Location: QtrQtr: SENE Section: 9 Township: 6S Range: 98W Meridian: 6
9. Field Name: SKINNER RIDGE Field Code: 77548

Completed Interval

FORMATION: WILLIAMS FORK - CAMEO Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 03/25/2012 End Date: 06/24/2012 Date of First Production this formation: 03/26/2012
Perforations Top: 4227 Bottom: 6537 No. Holes: 300 Hole size: 35/100

Provide a brief summary of the formation treatment: Open Hole: []

Perforated and fractured the Williams Fork - Cameo formation in 11 stages. Pumped a total of 41,328 bbl of clean produced water and 1,081,384 lbs of sand.

This formation is commingled with another formation: [] Yes [X] No

Total fluid used in treatment (bbl): 41328 Max pressure during treatment (psi): 6403
Total gas used in treatment (mcf): Fluid density at initial fracture (lbs/gal): 8.43
Type of gas used in treatment: Min frac gradient (psi/ft):
Total acid used in treatment (bbl): Number of staged intervals: 11
Recycled water used in treatment (bbl): 41328 Flowback volume recovered (bbl):
Fresh water used in treatment (bbl): Disposition method for flowback: RECYCLE
Total proppant used (lbs): 1081384 Rule 805 green completion techniques were utilized: [X]

Reason why green completion not utilized:

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 07/14/2012 Hours: 24 Bbl oil: 0 Mcf Gas: 960 Bbl H2O: 735
Calculated 24 hour rate: Bbl oil: 0 Mcf Gas: 960 Bbl H2O: 735 GOR: 0
Test Method: Flowtest Casing PSI: 1430 Tubing PSI: 800 Choke Size: 24/64
Gas Disposition: SOLD Gas Type: DRY Btu Gas: 1080 API Gravity Oil: 0
Tubing Size: 2 + 3/8 Tubing Setting Depth: 5902 Tbg setting date: 07/13/2012 Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: [] Yes [] No If yes, number of sacks cmt

** Bridge Plug Depth: ** Sacks cement on top: ** Wireline and Cement Job Summary must be attached.

Comment:

| |
|--|
| |
|--|

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Janet Howell
Title: Technical Assistant Date: _____ Email janeth@chevron.com
:

Attachment Check List

| Att Doc Num | Name |
|-------------|------|
| | |

Total Attach: 0 Files

General Comments

| <u>User Group</u> | <u>Comment</u> | <u>Comment Date</u> |
|--------------------------|-----------------------|----------------------------|
| | | |

Total: 0 comment(s)