

FORM
5Rev
02/08**State of Colorado****Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400293250

Date Received:

06/07/2012

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 47120

4. Contact Name: JOEL MALEFYT

2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP

Phone: (720) 929-6828

3. Address: P O BOX 173779

Fax: (720) 929-7828

City: DENVER State: CO Zip: 80217-

5. API Number 05-123-33784-00

6. County: WELD

7. Well Name: STREAR

Well Number: 17-10

8. Location: QtrQtr: NENE Section: 10 Township: 2N Range: 67W Meridian: 6

Footage at surface: Distance: 1024 feet Direction: FNL Distance: 1146 feet Direction: FEL

As Drilled Latitude: 40.157059 As Drilled Longitude: -104.871235

GPS Data:

Data of Measurement: 03/26/2012 PDOP Reading: 1.5 GPS Instrument Operator's Name: Renee Doiron

** If directional footage at Top of Prod. Zone Dist.: 1563 feet. Direction: FNL Dist.: 1603 feet. Direction: FEL

Sec: 10 Twp: 2N Rng: 67W

** If directional footage at Bottom Hole Dist.: 1561 feet. Direction: FNL Dist.: 1602 feet. Direction: FEL

Sec: 10 Twp: 2N Rng: 67W

9. Field Name: WATTENBERG

10. Field Number: 90750

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 02/28/2012 13. Date TD: 03/01/2012 14. Date Casing Set or D&A: 03/03/2012

15. Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 7750 TVD** 7664 17 Plug Back Total Depth MD 7712 TVD** 7626

18. Elevations GR 4924 KB 4939

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

CBL; HRI; CD-CN-ML

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	8+5/8	24	0	732	460	15	732	CALC
1ST	7+7/8	4+1/2	11.6	0	7,734	1,093	420	7,734	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____					
Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom
Details of work:					

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES					
FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PARKMAN	4,044		<input type="checkbox"/>	<input type="checkbox"/>	
SUSSEX	4,443		<input type="checkbox"/>	<input type="checkbox"/>	
SHANNON	5,010		<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	7,303		<input type="checkbox"/>	<input type="checkbox"/>	
FORT HAYS	7,545		<input type="checkbox"/>	<input type="checkbox"/>	
CODELL	7,567		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

--

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: JOEL MALEFYT

Title: REGULATORY ANALYST Date: 6/7/2012 Email: JOEL.MALEFYT@ANADARKO.COM

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400293275	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400293276	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400293250	FORM 5 SUBMITTED	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400293273	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)