



State
of
Colorado



Andrews, David <david.andrews@state.co.us>

Eck 12-90-1 #1 (API # 05-051-06107) surface cement

2 messages

Catherine Dickert <cdickert@sginterests.com>
To: david.andrews@state.co.us

Tue, Oct 9, 2012 at 4:41 PM

Eck 12-90-1 #1 (API # 05-051-06107)

Surface casing and cementing – Date: September 24, 2012

- Hole size – 12 ¼”
- Casing size - 9 5/8”
- Casing setting depth – 415.5’
- Stage tool setting depth (if used) - None
- Flowing casing/lift pressure immediately prior to bumping the plug – 142 psi
- Pressure to bump plug and time held before bleeding down pressure - 1153 psi
- Sacks, yield, and slurry weight of lead cement, tail cement, and top-out cement (if any)

Lead cement – 55 sks 12.3 PPG 2.33 cu ft/sk

Tail cement – 70 sks 12.8 PPG 2.07 cu ft/sk

Top-out cement – 17 sks 12.8 PPG lime

- Barrels of cement circulated to surface (if any) – 12 BBL

Catherine Dickert

Environmental and Permitting Manager

SG Interests, I Ltd.

1485 Florida Road, C202

Durango, CO 81301

Phone: 970-385-0696

Mobile: 970-209-6464

Fax: 970-252-0636