



State
of
Colorado



Andrews, David <david.andrews@state.co.us>

Hughes 11-90-26 #2 API# 05-051-06106 surface cement report

1 message

Catherine Dickert <cdickert@sginterests.com>

Wed, Oct 10, 2012 at 10:20 AM

To: david.andrews@state.co.us

Hughes 11-90-26 #2 (API # 05-051-06106)

Surface casing and cementing – Date: October 10, 2012

- Hole size – 12 ¼”
- Casing size - 9 5/8”
- Casing setting depth – 415.10’
- Stage tool setting depth (if used) - None
- Flowing casing/lift pressure immediately prior to bumping the plug – 117 psi
- Pressure to bump plug and time held before bleeding down pressure - 970 psi
- Sacks, yield, and slurry weight of lead cement, tail cement, and top-out cement (if any)

Lead cement – 140 sks 12.8 PPG 2.07 cu ft/sk slurry volume 51.6 bbls

Top-out cement – 20 sks 15.8 ppg w/2% CaCl slurry volume 4.4 bbls

- Barrels of cement circulated to surface (if any) – 20 BBL

Catherine Dickert

Environmental and Permitting Manager

SG Interests, I Ltd.

1485 Florida Road, C202

Durango, CO 81301

Phone: 970-385-0696

Mobile: 970-209-6464

Fax: 970-252-0636

cdickert@sginterests.com